CONTRACT NO. 64647

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	158
STA. 405+60	TO STA. 412+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DRAIN — SURVEYED / DRAWN / ALIGNMENT CHECKED / GRADES CHECKED / STRUCTURE NOTATIONS CHKD / NOTE BOOK / NO. / BY / DATE

PROFILE — SURVEYED / DRAWN / ALIGNMENT CHECKED / GRADES CHECKED / STRUCTURE NOTATIONS CHKD / NOTE BOOK / NO. / BY / DATE

CITY OF ROCK ISLAND
CITY OF MOLINE

VALLEY VIEW DRIVE

RAMP 2

MILAN BELTWAY

MATCH LINE STA. 405+60

MATCH LINE STA. 412+00

STA 406+00.00
DR. STR.-T4-T2OF&G
GRATE ELEV.= 584.40

STA 408+50.00
DR. STR.-T4-T2OF&G
GRATE ELEV.= 588.00

STA 411+00.00
DR. STR.-T4-T2OF&G
GRATE ELEV.= 591.60

12'-SS-CLA-T2-12"
℄ 588.46 - 583.00
CONC COLLAR 0.11 C.Y.

STA. 166+70.68 57.06' RT
PRECAST REINF. CONC.
END SECTIONS 12"
℄ ELEV. 588.46

STA. 167+48.22 62.02' RT
PRECAST REINF. CONC.
END SECTIONS 12"
℄ ELEV. 585.45

24'-SS-CLA-T2-12"
℄ 583.00 - 585.45
CONC. COLLAR 0.11 C.Y.

78'-SS-CLA-T2-12"
℄ 578.89 - 578.55

STA. 406+00.00 81.73 RT
PRECAST REINF. CONC.
END SECTIONS 12"
℄ ELEV. 578.55

STA. 408+50.00 83.55 RT
PRECAST REINF. CONC.
END SECTIONS 12"
℄ ELEV. 580.55

80'-SS-CLA-T2-12"
℄ 580.90 - 580.55

94'-SS-CLA-T3-12"
℄ 581.01 - 580.60

STA. 411+00.00 98.18 RT
PRECAST REINF. CONC.
END SECTIONS 12"
℄ ELEV. 580.60

P.C. STA = 388+51.29
P.T. STA = 414+70.16

MILAN BELTWAY DRAINAGE DETAILS – STA. 405+60 TO 412+00