

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*** (70X,71X)RS-1, (71X-VBR)DM		CONTRACT NO. 66225		

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE				
				80% FED 20% STATE ROADWAY	1000 DETOUR ROADWAY WORK 50% STATE 50% CITY	1000 LINCOLN AVENUE IMPROVEMENTS 100% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY	PARKING LANE Y025 50% STATE 50% CITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETERS)	UNIT	235	235				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	574	574				
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6				
20101000	TEMPORARY FENCE	FOOT	1,500	1500				
20101200	TREE ROOT PRUNING	EACH	100	100				
20200100	EARTH EXCAVATION	CU YD	7,490	7,467		23		
20400800	FURNISHED EXCAVATION	CU YD	16,122	16,122				
20800150	TRENCH BACKFILL	CU YD	3,134	3,098		36		
20900110	POROUS GRANULAR BACKFILL	CU YD	227	227				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	28,593	28,418		175		
21300010	EXPLORATION TRENCH SPECIAL	FOOT	500	500				
25000110	SEEDING, CLASS 1A	ACRES	5.64	5.6		0.04		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	757	754		3		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	757	754		3		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	757	754		3		
25100115	MULCH, METHOD 2	ACRE	5.6	5.6				
25100630	EROSION CONTROL BLANKET	SQ YD	1,283	1,283				
25200110	SODDING, SALT TOLERANT	SQ YD	20,849	20,849				
25200200	SUPPLEMENTAL WATERING	UNIT	312	312				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,976	2,976				
28000300	TEMPORARY DITCH CHECKS	EACH	58	58				
28000500	INLET AND PIPE PROTECTION	EACH	103	99		4		
28100107	STONE RIPRAP, CLASS A4	SQ YD	105	105				
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	105	105				
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	10110	9950				160
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	828	828				

DESIGN	INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

FILE NAME = I:\0194\DRAWINGS\PART 5A SOUTH PART\SUMMARY.dgn
 PLOT SCALE = 1/27/2005
 PLOT DATE = 1/27/2005
 PLOT TIME = 9:55:04 AM
 OPERATOR = gregj

DATE: _____
 BY: _____
 CHECKED: _____
 DATE: _____
 DATE: _____
 DATE: _____

CHECKS	INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU 6108 (IL. RTE. 351)
 SECTION (70X, 71X)RS-1, (71X-VBR)DM
 LASALLE COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE: 01/03/03

DRAWN BY: JETT
 DESIGNED BY: KUNTZMAN
 CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
 OF ENGINEERS

COMPUTER FILE NO.
 SUMMARY-01
 PROJECT 01194.B.S
 10/30/03-JLJ