F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	••••	LASALLE	679	6
STA. ———	TO STA. ———			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

••• (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = J:\01941\DRAWINGS\PART_B\SOUTH PART\SUMMARY.dgn
PLOT SCALE = 1
PLOT DATE = 1/26/2005
PLOT TIME = 2:18:13 PM
OPERATOR = gregj
DRV = XES_8850_ENG.ctb

PROFILE		DATE
SURVEYED		
DRAWN		
GRADES CHECKED		
NOTE BOOK		
STRUCTURE NOTATIONS CHKD		
NO.		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QTY.	CONSTRUCTION CODE: I 000 80% FED 20% STATE ROADWAY	STRUCTURE REMOVAL	I000 DETOUR ROADWAY WORK 50% STATE 50% CITY	I000 LINCOLN AVENUE IMPROVEMENTS 100% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY	PARKING LANE Y025 50% STATE 50% CITY
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	48	48					
35100100	AGGREGATE BASE COURSE, TYPE A	TON	776	676			100		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	3,817	3,657					160
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4803	3958		601	244		
40600300	AGGREGATE (PRIME COAT)	TON	91	75		15	1		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	119	111		8			
40600895	CONSTRUCTION TEST STRIP	EACH	1	1					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	3603	3603					
40600985	PORTLAND CEMENT CONCRETE SURFACE COURSE REMOVAL - BUTT JOINT	SQ YD	102	102					
40600990	TEMPORARY RAMP	SQ YD	584	584					
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1,051	1,051					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2568	2,517			51		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2,805	2,805					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	71,033	67,981				3,052	
42400610	TEMPORARY SIDEWALK	SQ FT	3,000	3,000					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	13,947	13,397			550		
44000100	PAVEMENT REMOVAL	SQ YD	326	326					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5,802	5,713			89		
44000300	CURB REMOVAL	FOOT	350	350					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15,303	15,253			50		
44000600	SIDEWALK REMOVAL	SQ FT	63,213	63,213					
44000700	APPROACH SLAB REMOVAL	SQ YD	213	213					
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	53	53					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3,986	3,986					
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	19	19					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
SPRINGFIELD & LINCOLN, ILLINOIS 62701
PROFESSIONAL DESIGN FIRM: ILL 184-000179
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 753-1818, (217) 753-1821 FAX, e-mail: GBSPRINGFIELD@GBSPRING.com

COMPUTER FILE NO.
SUMMARY-02

PROJECT 01194_B_S
10/30/03-JLJ

J:\01941\DRAWINGS\PART_B\SOUTH PART\SUMMARY.dgn 1/26/2005 2:17:14 PM gregj (CTB6)