F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	9
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DESIGN

INT.	DATE	REASON

PLOTS & CHECKS

INT.	DATE	NO.	REASON

CHECKS

INT.	DATE	REASON

FILE NAME = J:\01194\DRAWINGS\PART-B\SOUTH PART\SUMMARY.dgn
PLOT SCALE = 1.0000
PLOT DATE = 1/27/2005
PLOT TIME = 4:59:55 PM
OPERATOR = grf
DRV = XES_8850_ENG.drv

PROFILE
SCANNED
PLOTTED
GRADES CHECKED
DRAINAGE NOTES
STRUCTURE NOTATNS CKD
NOTE BOOK
NO. BY DATE

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 00C 80% FED 20% STATE ROADWAY		I000 DETOUR ROADWAY WORK 50% STATE 50% CITY	I000 LINCOLN AVENUE IMPROVEMENTS 100% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY	PARKING LANE Y025 50% STATE 50% CITY
55100500	STORM SEWER REMOVAL 12"	FOOT	954	954					
55100700	STORM SEWER REMOVAL 15"	FOOT	283	283					
55100900	STORM SEWER REMOVAL 18"	FOOT	76	76					
55101200	STORM SEWER REMOVAL 24"	FOOT	55	55					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	41	41					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	33	33					
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	35	35					
60220300	MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	16	16					
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	4	4					
60222200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 15 FRAME AND LID	EACH	3	3					
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	107	107					
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	22	22					
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	9	9					
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	5	5					
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	71	71					
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	14	14					
60240320	INLETS, TYPE B, TYPE 15 FRAME AND LID	EACH	21	17			4		
60240324	INLETS, TYPE B, TYPE 20 FRAME AND GRATE	EACH	4	4					
60240370	INLETS, TYPE B, WITH SALVAGED FRAME & GRATE	EACH	1	1					
60243910	INLETS, SPECIAL, TYPE 3 FRAME AND GRATE	EACH	2	2					
60255500	MANHOLES TO BE ADJUSTED	EACH	10	8			2		

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
MANAGEMENT/SYSTEMS DESIGN
TRANSPORTATION PLANNING
PROFESSIONAL SERVICES FOR CITIES
SPECIALIZING IN STRUCTURAL ENGINEERING CONSULTATION
(217) 753-6641, (217) 753-6321 (FAX), 1 (800) 747-6641 (OUTSIDE ILLINOIS)

COMPUTER FILE NO.
SUMMARY-05

PROJECT 01194.B.S
10/30/03-JLJ