F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	11
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DESIGN

INT.	DATE	REASON

PLOTS & CHECKS

INT.	DATE	NO.	REASON

CHECKS

INT.	DATE	REASON

FILE NAME = J:\01194\DRAWINGS\PART_B\SOUTH_PART\SUMMARY.dgn
PLOT SCALE = 1 '/ 1/27/2005
PLOT DATE = 4:59:13 PM
DRV = XES_8850_ENG.plt
OPERATOR = JETT
DGN = DP_1

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / DRAWN / NOTED / STRUCTURE — NOTATIONS OTHRD
NOTE BOOK
NO.

SUMMARY OF QUANTITIES

URBAN

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 000 80% FED 20% STATE ROADWAY	X071 STRUCTURE REMOVAL	I000 DETOUR ROADWAY WORK 50% STATE 50% CITY	I000 LINCOLN AVENUE IMPROVEMENTS 100% CITY	SFTY-1B SIDEWALK 50% STATE 50% CITY	PARKING LANE Y025 50% STATE 50% CITY
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	635	635					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,454	4,454					
• 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	344	344					
• 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19,185	19,185					
• 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,936	5,936					
• 70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,410	1,410					
• 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,494	2,494					
• 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	754	754					
• 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14,599	14,599					
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTER AND SYMBOLS	SQ FT	344	344					
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,785	16,785					
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,936	5,936					
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,410	1,410					
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,494	2,494					
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	699	699					
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	169	169					
• 78200300	PRISMATIC CURB REFLECTOR	EACH	18	18					
• 7830040~~5~~	THERMOPLASTIC PAVEMENT MARKING REMOVAL	FOOT	1,258	1,258					
X0301834	STORM SEWER TO BE FILLED	FOOT	1,641	1,641					
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	31	31					
X0323449	REMOVE EXISTING WATER VALVE	EACH	1	1					
X0930400	STORM SEWER WATER MAIN 12"	FOOT	3,456	3,456					
X0930450	STORM SEWER WATER MAIN 15"	FOOT	2,155	2,155					

*SPECIALTY ITEMS

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
300 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62702
PROFESSIONAL DESIGN FIRM NO. 184-000775
PROFESSIONAL SERVICE CORPORATION
(217) 793-3848 (217) 793-3921 (FAX) — contact@greenebradford.com

COMPUTER FILE NO. SUMMARY-07
PROJECT 01194.B_S
10/30/03-JLJ

...\PART_B\SOUTH_PART\SUMMARY.dgn 1/27/2005 4:59:13 PM User = jkntz