DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = $FILE$
PLOT SCALE = $SCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE

NOTE BOOK
NO. _____

	BY	DATE
SURVEYED		
PLOTTED		
CHECKED		
GRADES NOTED		
S.M. NOTED		
STRUCTURE NOTATNS CHKD		

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	29
STA. ———	TO STA. ———			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DRAINAGE STRUCTURE SCHEDULE

LOCATION	MANHOLES, TYPE A, 4'-DIAMETER			MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 5'-DIAMETER			MANHOLES, TYPE A, 6'-DIAMETER		INLETS, TYPE A				INLETS, TYPE B						INLETS, TYPE B, SPECIAL, TYPE 3 FRAME AND GRATE	SANITARY SEWER MANHOLES, TYPE A, TYPE 1 FRAME, CLOSED LID
	TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 15 FRAME AND LID		TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 15 FRAME AND LID	TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE	TYPE 20 FRAME AND GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE	TYPE 15 FRAME AND LID	TYPE 20 FRAME AND GRATE	WITH SALVAGED GRATE		
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA. 143+63, 24.5' LT.														1							
STA. 144+25, 30' RT.												1									
STA. 144+85, 18.5' RT.															1						
STA. 144+85, 18.5' LT.															1						
STA. 145+24.17, 52' LT.			1																		
STA. 145+27.17, 55' RT.															1						
STA. 145+62.47, 50.25' LT.																	1				
STA. 145+65.27, 55' RT.															1						
STA. 145+66.27, 50.04' LT.					1																
STA. 145+84, 30.15' LT.	1																				
STA. 145+90.08, 21.03' RT.											1										
STA. 146+03, 24.5' LT.											1										
STA. 146+03, 28.5' LT.	1																				
STA. 146+72, 18.5' RT.											1										
STA. 146+72, 24.5' LT.															1						
STA. 146+72, 28.5' LT.	1																				
STA. 147+74, 24.5' LT.											1										
STA. 147+74, 28.5' LT.	1																				
STA. 148+14, 18.5' RT.															1						
STA. 148+14, 24.5' LT.															1						
STA. 148+14, 28.5' LT.	1																				
STA. 148+25, 32' RT.												1									
STA. 149+28.66, 47' LT.											1										
STA. 160+44, 20.5' LT.											1										
STA. 162+47.99, 35' RT.											1										
STA. 162+84.94, 22' RT															1						
STA. 162+89.07, 20.91' LT.											1										
STA. 163+10, 26' RT.	1																				
STA. 163+10, 13.55' RT.											1										
STA. 163+30.48, 40.40' LT.			1																		
STA. 163+62.08, 34.47' LT.			1																		
STA. 163+81, 31.04' LT.																					1
STA. 163+88, 26' RT.	1																				
STA. 163+88, 11.54' RT.			1																		
STA. 163+88, 17.46' LT.			1																		
STA. 164+68, 26' RT.	1																				
STA. 164+68, 17.5' RT.															1						
STA. 164+68, 17.5' LT.											1										
STA. 165+17, 17.5' LT.											1										
STA. 165+24, 26' RT	1																				

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
3001 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
POST OFFICE BOX 19428 ZIP 62794-9428
PROFESSIONAL DESIGN FIRM 184.001039
(217) 793-6644, (217) 793-6633 (FAX), (800) 747-6644
e-mail: GBSPRINGFIELD@GREENEANDBRADFORD.COM

COMPUTER FILE NO.
SCHEDULE_04

PROJECT 01194_B_S
10/30/03-JLJ

\part_f\south part\schedule.dgn 12/2/2004 6:25:14 PM User = greg