DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = u:\ow9a\drawings\part 3\south part 3\schedule.dgn
PLOT SCALE = 1.0000 '/ IN.
PLOT DATE = 1/27/2005
PLOT TIME = 4:55:30 PM
OPERATOR = gregj

PROFILE: SURVEYED / PLOTTED / CHECKED / NOTE BOOK / NO. / NOTED / STRUCTURE NOTATING GRADE / BY / DATE

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	37
STA. ————	TO STA. ————			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DRAINAGE STRUCTURE SCHEDULE

LOCATION	MANHOLES, TYPE A, 4'-DIAMETER			MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 5'-DIAMETER			MANHOLES, TYPE A, 6'-DIAMETER		INLETS, TYPE A				INLETS, TYPE B						INLETS, TYPE B, SPECIAL, TYPE 3 FRAME AND GRATE	SANITARY SEWER MANHOLES, TYPE A, TYPE 1 FRAME, CLOSED LID
	TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 15 FRAME AND LID		TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 15 FRAME AND LID	TYPE 1 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE	TYPE 20 FRAME AND GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3 FRAME AND GRATE	TYPE 8 GRATE	TYPE 15 FRAME AND LID	TYPE 20 FRAME AND GRATE	WITH SALVAGED GRATE		
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
STA. 225+48, 34.48' LT.											1										
STA. 225+50, 31' RT.					1																
STA. 225+50, 20' RT.													1								
STA. 226+09, 20' RT.											1										
STA. 226+15, 20' RT.															1						
STA. 226+15, 35' RT.					1																
STA. 226+21, 20' RT.											1										
STA. 226+85, 35' RT.					1																
STA. 226+85, 20' RT.											1										
STA. 228+53.32, 35' RT.					1																
STA. 230+21.94, 64.43' LT.								1													
STA. 232+75, 49.15' LT.					1																
STA. 232+75, 57' LT.									1												
STA. 233+50, 48' LT.						1															
STA. 234+00, 43.5' LT.		1																			
STA. 235+00, 41' LT.		1																			
STA. 236+25, 45' LT.		1																			
STA. 237+00, 43' LT.		1																			
STA. 238+00, 41' LT.		1																			
STA. 239+00, 37.5' LT.		1																			
RACCUGLIA ROAD																					
STA. 48+01, 23.5' RT.											1										
STA. 48+01, 20.01' LT.															1						
STA. 48+51, 23.5' RT.											1										
STA. 48+52, 28.27' LT.											1										
STA. 48+72, 31.82' LT.															1						
STA. 48+74, 23.5' RT.															1						
STA. 49+00.75, 23.5' RT.																				1	
STA. 49+03.56, 37.37' LT.																				1	
STA. 49+27.52, 45.46' LT.															1						
STA. 49+32.37, 23.50' RT.											1										
TOTALS	41	33	35	3	16	4	3	2	1	1	107	22	9	5	71	14	17	4	1	2	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
2100 CAHILL TOLLWAY DRIVE
SPRINGFIELD, ILLINOIS 62702
PROFESSIONAL DESIGN FIRM NO. 184.001379
(217) 793-8400 (217) 793-8477 FAX e-mail: info@greene-bradford.com

COMPUTER FILE NO. SCHEDULE_12
PROJECT 01194.8.S
10/30/03-JLJ

u:\part 3\south part\schedule.dgn 1/27/2005 4:55:30 PM User gregj