F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	52
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

TRENCH BACKFILL SCHEDULE

LOCATION			1 PIPE SIZE	2 TOP ELEV.	3 PIPE INV.	4 PAVEMENT THICKNESS	5 TRENCH DEPTH	6 BACKFILL PER FOOT	7 TRENCH LENGTH	8 VOLUME	9 LT. PATCH LENGTH	10 LT. PATCH WIDTH	11 LT. PATCH AREA	12 LT. PATCH TYPE	13 RT. PATCH LENGTH	14 RT. PATCH WIDTH	15 RT. PATCH AREA	16 RT. PATCH TYPE
STATION	ROAD	STR #	INCHES	FOOT	FOOT	FOOT	FOOT	CU YD/FT.	FOOT	CU YD	FOOT	FOOT	SQ YD		FOOT	FOOT	SQ YD	
STA. 223+46, 37' LT. & 34' LT.	ILL RTE 35	PIPE CULVERT	2-15	628.00	626.17	0.67	1.16	0.242	24	5.8								
STA. 224+88, 35' RT. TO STA. 225+50, 35' RT.	ILL RTE 35	#430 TO #432	30	626.05	619.63	0.67	5.75	0.875	40	35.0								
STA. 226+09, 20' RT. TO STA. 226+15, 20' RT.	ILL RTE 35	#435 TO #436	12	627.31	624.27	0.67	2.37	0.169	40	6.8								
STA. 226+21, 20' RT. TO STA. 226+15, 20' RT.	ILL RTE 35	#437 TO #436	12	627.31	624.27	0.67	2.37	0.169	40	6.8								
STA. 236+25, 45' LT. TO STA. 235+00, 41' LT.	ILL RTE 35	#458 TO #459	30	631.50	620.10	0.67	10.73	1.998	38	75.9								
STA. 236+11.93, 49.06' RT.	ILL RTE 35	PIPE CULVERT	42	632.25	626.28	0.67	5.30	0.690	34	23.5		.			22	7.8	19.1	III
STA. 238+00, 41' LT. TO STA. 237+00, 43' LT.	ILL RTE 35	#456 TO #457	24	630.80	623.60	0.67	6.53	1.035	39	40.4								
STA. 238+98, 39' RT.	ILL RTE 35	PIPE CULVERT	24	631.50	628.69	0.5	2.31	0.116	28	3.2								
STA. 240+68, 36.69' LT. TO STA. 239+00, 37.5' LT.	ILL RTE 35	PRCFES TO #455	24	632.90	628.28	0.67	3.95	0.346	48	16.6	43	6.0	28.7	IV				
STA. 240+64, 37.63' RT.	ILL RTE 35	PIPE CULVERT	24	632.40	629.36	0.5	2.54	0.137	28	3.8								
STA. 241+46, 36' RT.	ILL RTE 35	PIPE CULVERT	24	632.60	629.69	0.5	2.42	0.118	12	1.4								
STA. 243+79, 35' RT.	ILL RTE 35	PIPE CULVERT	18	633.20	630.72	0.67	1.82	0.105	28	2.9								
STA. 244+82, 34.5' LT.	ILL RTE 35	PIPE CULVERT	18	633.90	631.13	0.67	2.10	0.118	28	3.3								
STA. 245+04, 35.5' RT.	ILL RTE 35	PIPE CULVERT	18	633.80	631.22	0.5	2.08	0.114	28	3.2								
RACCUGLIA ROAD																		
STA. 48+01, 23.5' RT. TO STA. 48+01, 20.01' LT.	ILL RTE 35	#447 TO #448	12	627.07	623.50	0.67	2.90	0.226	39	8.8	18	4.8	9.6	II	15	4.8	8.0	II
STA. 48+52, 28.27' LT. TO STA. 48+72, 31.82' LT.	ILL RTE 35	#452 TO #453	12	626.64	622.99	0.67	2.98	0.234	17	4.0								
STA. 48+51, 23.5' RT. TO STA. 48+74, 23.5' RT.	ILL RTE 35	#449 TO #450	12	626.75	623.63	0.67	2.45	0.178	21	3.7								
STA. 48+72, 31.82' LT. TO STA. 49+03.56, 37.37' LT.	ILL RTE 35	#453 TO #454	12	626.56	622.49	0.67	3.40	0.277	25	6.9								
STA. 48+74, 23.5' RT. TO STA. 49+00.75, 23.5' RT.	ILL RTE 35	#450 TO #451	12	626.69	623.23	0.67	2.79	0.214	29	6.2								
STA. 49+01.60 RT. & RT.	ILL RTE 35	PIPE CULVERT	3'X2'	626.58	622.13	0.67	3.78	0.409	68	27.8	22	7.0	17.1	III	19	7.0	14.8	II
											TOTAL I	18.7						
											TOTAL II	1233.7						
											TOTAL III	257.3						
											TOTAL IV	137.0						
TOTALS										3098.1								

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATE	NO. REASON

FILE NAME = $FILE$
PLOT SCALE = $ptscale$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE	BY	DATE
SURVEYED		
PLOTTED		
GRADES CHECKED		
B.M. NOTED		
STRUCTURE NOTATNS CHKD		
NOTE BOOK NO.		

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
2020 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM 184-000278
PROFESSIONAL ENGINEERING CORPORATION
(217) 793-8844, (217) 793-3217 (FAX) E-MAIL: mail@greenebradford.com

COMPUTER FILE NO.
SCHEDULE_38

PROJECT 01194_B_S
10/30/03-JLJ

\part_b\south part\schedule.dgn 12/22/2004 8:25:15 PM Lisa (greg)