F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	••••	LASALLE	679	56
STA. ————		TO STA. ————		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

••• (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = $FILE$
PLOT SCALE = $pltscale$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE	BY	DATE
SURVEYED		
PLAN PREP.		
GRADES CHECKED		
STRUCTURE NOTATIONS CHKD		
NOTE BOOK NO.		

REFLECTOR SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKERS	PRISMATIC CURB REFLECTOR
	EACH	EACH
MAINLINE		
STA. 134+72 TO STA. 139+00	9	
STA. 139+00 TO STA. 144+00	7	
STA. 144+00 TO STA. 149+00	5	
STA. 149+00 TO STA. 154+00	8	
STA. 154+00 TO STA. 159+00	4	18
STA. 159+00 TO STA. 164+00	11	
STA. 164+00 TO STA. 169+00	6	
STA. 169+00 TO STA. 174+00	6	
STA. 174+00 TO STA. 178+00	5	
STA. 178+00 TO STA. 182+50	6	
STA. 182+50 TO STA. 187+00	6	
STA. 187+00 TO STA. 192+00	6	
STA. 192+00 TO STA. 197+00	6	
STA. 197+00 TO STA. 202+00	6	
STA. 202+00 TO STA. 207+00	11	
STA. 207+00 TO STA. 212+00	6	
STA. 212+00 TO STA. 217+00	10	
STA. 217+00 TO STA. 222+00	10	
STA. 222+00 TO STA. 227+00	8	
STA. 227+00 TO STA. 232+00	9	
STA. 232+00 TO STA. 237+00	6	
STA. 237+00 TO STA. 242+00	6	
STA. 242+00 TO STA. 247+00	7	
RACCUGLIA ROAD		
STA. 45+60 TO STA. 50+00	5	
TOTAL	169	18

CULVERT & RIPRAP SCHEDULE

LOCATION	PRECAST BOX CULVERT (M273)		PIPE CULVERTS, CLASS A, TYPE 1					STONE RIPRAP CLASS A 4	FILTER FABRIC FOR USE WITH RIPRAP
	9' X 5'	3' X 2'	15"	18"	24"	30"	42"		
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ YD	SQ YD
MAINLINE									
STA. 223+46, 31.75' LT. & 34.75' LT.			84						
STA. 229+42 RT. & LT.	252							105	105
STA. 232+93, RT. & LT.						14			
STA. 236+11.93, 49.06' RT.							69		
STA. 238+98, 39' RT.					67				
STA. 240+64, 36.53' RT.					57				
STA. 241+46, 3475' RT.					35				
STA. 243+79, 33.25' RT.				37					
STA. 244+82, 33.25' LT.				40					
STA. 245+04, 33.35' RT.				33					
RACCUGLIA ROAD									
STA. 49+01.60 RT. & RT.		84							
TOTALS	252	84	84	110	159	14	69	105	105

STORM SEWER FILLING SCHEDULE

LOCATION	STORM SEWER FILLING
	FOOT
STA. 137+68.57, 17.04' RT. TO STA. 137+72.74, 17.69' LT.	35
STA. 137+72.74, 17.69' LT. TO STA. 137+35.29, 34.51' LT.	40
STA. 141+19.10, 24.56' RT. TO STA. 141+26.58, 58.44' LT.	83
STA. 141+05.79, 18.13' LT. TO STA. 141+26.58, 58.44' LT.	16
STA. 143+29.74, 16.36' RT. TO STA. 143+26.53, 18.3' LT.	35
STA. 145+84.87, 16.23' RT. TO STA. 145+65.34, 37.81' RT.	29
STA. 145+65.34, 37.81' RT. TO STA. 145+27.21, 38.44' RT.	38
STA. 145+65.34, 37.81' RT. TO STA. 145+27.88, 45.15' LT.	84
STA. 162+51.77, 33.35' RT. TO STA. 163+25.45, 20.83' LT.	92
STA. 178+93.38, 19.90' RT. TO STA. 178+74.63, 38.38' LT.	61
STA. 183+08.24, 20.60' RT. TO STA. 183+15.81, 15.08' RT.	9
STA. 182+90.55, 25.86' LT. TO STA. 183+15.81, 15.08' RT.	48
STA. 183+17.99, 24.21' LT. TO STA. 183+15.81, 15.08' RT.	39
STA. 193+30.76, 12.72' RT. TO STA. 193+30.60, 11.80' LT.	25
STA. 203+05.79, 11.41' RT. TO STA. 203+04.94, 12.34' LT.	24
STA. 203+04.94, 12.34' LT. TO STA. 203+09.00, 32' LT.	20
STA. 206+51.93, 37.75' LT. TO STA. 206+25.49, 36.47' LT.	26
STA. 215+76.18, 21.31' RT. TO STA. 216+24.18, 21.31' RT.	48
STA. 216+24.18, 21.31' RT. TO STA. 218+16.94, 21.64' RT.	193
STA. 218+16.94, 21.64' RT. TO STA. 218+93.59, 23.53' RT.	77
STA. 218+93.59, 23.53' RT. TO STA. 219+64.95, 28.04' RT.	72
STA. 219+64.95, 28.04' RT. TO STA. 221+81.17, 27.66' RT.	216
STA. 219+23.63, 29.68' RT. TO STA. 219+45.07, 29.99' RT.	21
STA. 221+81.17, 27.66' RT. TO STA. 224+91.17, 27.66' RT.	310
TOTALS	1641

PIPE CULVERT REMOVAL SCHEDULE

LOCATION	PIPE CULVERT REMOVAL
	FOOT
MAINLINE	
STA. 223+46, 30' LT	51
STA. 227+23, 39' LT	45
STA. 236+12, 41' RT	86
STA. 237+62, 36.5' LT	40
STA. 238+98, 34' RT	42
STA. 240+30, 34' LT	60
STA. 240+64, 33' RT	39
STA. 241+46, 33' RT	39
STA. 243+79, 30' RT	38
STA. 244+82, 32' LT	60
STA. 245+04, 30' RT	40
TOTALS	540

TRENCH DRAIN SCHEDULE

LOCATION	CONCRETE HEADWALL REMOVAL
	EACH
STA. 217+51, 45' RT.	24
TOTALS	24

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT. HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
SPRINGFIELD, ILLINOIS 62704
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000178
PROFESSIONAL SERVICES INDUSTRY CORPORATION
VOICE 217-544-7464, FACSIMILE 217-544-7482, E-MAIL — mail@greenebradford.com

COMPUTER FILE NO. SCHEDULE_19
PROJECT 01194_B_S
10/30/03-JLJ

\part_jt\south part\schedule.dgn 12/2/2024 6:29:15 PM User = gregj