F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	****	LASALLE	679	67
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*** (70X,71X)RS-1, (71X-VBR)DM
CONTRACT NO. 66225

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

FILE NAME = $FILE$
PLOT SCALE = $SCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE	BY	DATE
SURVEYED		
PLOTTED		
ALIGNMENT CHECKED		
NOTE BOOK NO.	B.M. NOTED	
	STRUCTURE NOTATIONS CHKD	

CHECKS		
INT.	DATE	REASON

EARTHWORK AND TOPSOIL SCHEDULE

LOCATION	EARTH EXCAVATION (C)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (F)	EARTHWORK BALANCE WASTE (+) OR SHRINKAGE (-)	TOPSOIL FURNISH AND PLACE, 4"
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	SQ. YD.
IL RTE 351					
STA. 135+65.00 TO STA. 137+41.11	127	96	5	91	446
STA. 137+41.11 TO STA. 141+42.56	286	215	36	179	728
STA. 141+42.56 TO STA. 145+43.27	264	198	29	169	725
STA. 145+43.27 TO STA. 149+44.71	299	225	26	199	422
STA. 160+00.00 TO STA. 163+45.54	136	102	14	88	273
STA. 163+45.54 TO STA. 170+53.17	252	189	200	-11	1490
STA. 170+53.17 TO STA. 172+20.16	59	45	31	14	264
STA. 172+20.16 TO STA. 174+79.52	116	87	59	28	389
STA. 174+79.52 TO STA. 178+92.09	134	101	87	14	646
STA. 178+92.09 TO STA. 183+29.08	155	117	107	10	569
STA. 183+29.08 TO STA. 186+46.18	219	165	32	133	304
STA. 186+46.18 TO STA. 189+73.64	199	150	29	121	407
STA. 189+73.64 TO STA. 192+99.61	190	143	16	127	431
STA. 192+99.61 TO STA. 196+33.20	231	174	29	145	529
STA. 196+33.20 TO STA. 199+65.56	166	125	52	73	453
STA. 199+65.56 TO STA. 206+39.74	521	391	57	334	914
STA. 206+39.74 TO STA. 209+55.76	323	243	33	210	383
STA. 209+55.76 TO STA. 212+82.27	216	162	90	72	380
STA. 212+82.27 TO STA. 216+07.98	138	104	93	11	646
STA. 216+07.98 TO STA. 219+34.80	107	81	127	-46	653
STA. 219+34.80 TO STA. 226+01.78	663	498	229	269	1662
STA. 226+01.78 TO STA. 232+66.27	852	639	19,658	-19,019	6569
STA. 232+66.27 TO STA. 236+11.90	385	289	395	-106	2056
STA. 236+11.90 TO STA. 240+30.08	377	283	123	160	1899
STA. 240+30.08 TO STA. 247+00.00	556	417	37	380	2188
RACCUGLIA ROAD	496	372	139	233	2641
TOTAL	7,467	5,611	21,733	-16,122	28067

PCC SIDEWALK, SPECIAL AND PIPE HANDRAIL, SPECIAL SCHEDULE

LOCATION	PCC SIDEWALK, SPECIAL	HANDRAIL REMOVAL	REMOVE AND REINSTALL EXISTING HANDRAIL	PIPE HANDRAIL,SPECIAL
	SQ FT	EACH	EACH	FOOT
STA. 139+03.50, RT.	7			
STA. 139+57, RT.	20			
STA. 139+97, RT.	13			
STA. 140+69.38, RT.	20			
STA. 143+73, RT.	16			
STA. 147+20.40, LT.	64	1		63
STA. 164+90, 29' RT. TO STA. 165+26, 29' RT.		1		
STA. 170+89.78, RT.	26	1		50
STA. 175+32.59, LT.	38	1		63
STA. 175+89.31, LT.	50		1	
STA. 179+84.32, LT.	26	1		50
STA. 180+55.84, RT.	26	1		50
STA. 180+69.19, LT.	38	1		63
STA. 181+00.00, LT.	26	1		50
STA. 181+55.04, LT.	38	1		63
TOTALS	408	9	1	452

PAVEMENT MARKING REMOVAL SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING REMOVAL
	FOOT
STA. 134+72 TO STA. 139+00	433
STA. 149+00 TO STA. 154+00	825
TOTALS	1258

CONCRETE HEADWALL REMOVAL SCHEDULE

LOCATION	CONCRETE HEADWALL REMOVAL
	EACH
MAINLINE	
STA. 232+90, RT & LT.	2
STA. 227+23, 39' LT.	2
RACCUGLIA ROAD	
STA. 48+49.30, 41.46' LT.	1
STA. 49+26.62, 58.64' LT.	1
STA. 49+51.94, 80.05' RT.	1
TOTALS	7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X, 71X)RS-1, (71X-VBR)DM
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
300 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000128
PROFESSIONAL DESIGN FIRM NO. 184-000128 CORPORATION
(217) 753-5893, (217) 753-5177 (FAX), E-MAIL: "GBINFO"@GREENEANDBRADFORD.COM

COMPUTER FILE NO.
SCHEDULE_02

PROJECT 01194_B_S
10/30/03-JLJ

.\cont_b\south part\schedule.dgn 12/2/2004 6:25:16 PM User = greg1