

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6194 (109)R	RS-4	KANKAKEE	82	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

66402

CODE NUMBER	PAY ITEMS	URBAN UNIT	80% FED 20% STATE QUANTITY
			I 000-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1000
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	814
20100500	TREE REMOVAL, ACRES	ACRE	3.7
20200100	EARTH EXCAVATION	CU YD	20447
20200200	ROCK EXCAVATION	CU YD	4873
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	CU YD	10210
20700110	POROUS GRANULAR EMBANKMENT	TON	1038
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	5879
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	59030
25000100	SEEDING, CLASS 1	ACRE	5.2
25000200	SEEDING, CLASS 2	ACRE	6.9
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1084
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1084
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1084
25100115	MULCH, METHOD 2	ACRE	12
25100630	EROSION CONTROL BLANKET	SQ YD	465
25200110	SODDING, SALT TOLERANT	SQ YD	1403
25200200	SUPPLEMENTAL WATERING	UNIT	12.7
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3684
28000300	TEMPORARY DITCH CHECKS	EACH	55
28000400	PERIMETER EROSION BARRIER	FOOT	12900
28000500	INLET AND PIPE PROTECTION	EACH	8
28100830	STONE DUMPED RIPRAP, CLASS B4	TON	148.1
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	73
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	12076
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	745
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	6231
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	288
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8823
40600300	AGGREGATE (PRIME COAT)	TON	39
40600895	CONSTRUCTING TEST STRIP	EACH	2
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	138.3
44000003	BITUMINOUS SURFACE REMOVAL, 3/4"	SQ YD	10401
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4033
44000100	PAVEMENT REMOVAL	SQ YD	19440
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	61
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	1121

CODE NUMBER	PAY ITEMS	URBAN UNIT	80% FED 20% STATE QUANTITY
			I 000-2A
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	266
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1739
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	4873
50105200	REMOVE EXISTING CULVERTS	EACH	6
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	383
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	4
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2
54010503	PRECAST CONCRETE BOX CULVERT 5' X 3'	FOOT	162
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	100
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	176
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	54
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	86
5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	12
54213453	END SECTIONS 18"	EACH	8
54213459	END SECTIONS 24"	EACH	2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4
60107600	PIPE UNDERDRAINS, 4"	FOOT	1100
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	61
60625800	ISLAND PAVEMENT (SPECIAL)	SQ YD	61
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	237.5
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	1
63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	38
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	954
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	46.8
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29545
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	593
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	375

PLAN SURVEYED BY DATE
 NOTE BOOK NO. CHECKED
 ALIGNED CHECKED
 PLUS FILE NAME

PROFILE SURVEYED BY DATE
 NOTE BOOK NO. CHECKED
 BAL. LOTTED
 PROFILE NOTATION SHOWN

*****DATE*****

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAU 6194 (ILLINOIS ROUTE 113)
 SUMMARY OF QUANTITIES
 (SHEET 1 OF 2)

SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY