

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6194 (109)R	RS-4	KANKAKEE	82	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

66402

CODE NUMBER	PAY ITEMS	URBAN UNIT	80% FED 20% STATE QUANTITY
			I 000-2A
* 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	251
* 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	79
* 70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	12032
* 72000100	SIGN PANEL - TYPE 1	SQ FT	91
* 73000100	WOOD SIGN SUPPORT	FOOT	216
* 73502000	RELOCATE GROUND-MOUNTED SIGN SUPPORT	EACH	3
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	46.8
* 78000200	THERMOPLASTIC PAVEMENT MARKING LINE - 4"	FOOT	29545
* 78000400	THERMOPLASTIC PAVEMENT MARKING LINE - 6"	FOOT	593
* 78000500	THERMOPLASTIC PAVEMENT MARKING LINE - 8"	FOOT	375
* 78000600	THERMOPLASTIC PAVEMENT MARKING LINE - 12"	FOOT	251
* 78000650	THERMOPLASTIC PAVEMENT MARKING LINE - 24"	FOOT	79
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	225
* 78200300	PRISMATIC CURB REFLECTOR	EACH	8
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4
* 78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	2
X0320590	GRATING FOR BOX CULVERT 5' X 3'	EACH	4
X0728700	GRATING FOR BOX CULVERT 6' X 3'	EACH	2
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	155
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	508
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	853
X4066526	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1291
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	702
X4073136	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 12 3/4"	SQ YD	11159
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	530
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

\* SPECIALTY ITEMS

PLAN	SURVEYED	BY	DATE
NOTE BOOK	ALIGNED		
NO.	BY		
	BY		
	BY		
	BY		
	BY		
	BY		
	BY		
	BY		

PROFILE	SURVEYED	BY	DATE
NOTE BOOK	ALIGNED		
NO.	BY		
	BY		
	BY		
	BY		
	BY		
	BY		
	BY		
	BY		

\*\*\*\*\*DATE\*\*\*\*\*

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAU 6194 (ILLINOIS ROUTE 113)  
SUMMARY OF QUANTITIES  
(SHEET 2 OF 2)

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY