

POROUS GRANULAR EMBANKMENT

TON	LOCATION
206.4	62+44 5' X 3' CROSSROAD RCBC
251.6	75+50 24" DETOUR RCP (TEMPORARY)
16.1	84+95 RT 18" DRIVEWAY RCP
353.8	94+41 6' X 3' CROSSROAD RCBC
157.2	104+28 5' X 3' CROSSROAD RCBC
52.4	104+28 LT 30" DETOUR RCP (TEMPORARY)
1037.5	TOTAL

TOPSOIL FURNISH AND PLACE, 4"

SQ YD	LOCATION
8964	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
5933	61+00.00 TO 79+00.00 RT
11988	79+00.00 TO 109+00.00 LT
14859	79+00.00 TO 114+00.00 RT
2237	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
1818	79+00.00 TO 85+00.00 LT
6500	85+00.00 TO 103+00.00 RT
1956	EAST DETOUR 62+00.00 TO 76+94.50 LT
2023	WEST DETOUR 98+37.01 TO 113+25.00 RT
755	TOWER ROAD 3+96.28 TO 7+00.00 LT
648	3+96.28 TO 7+00.00 RT
412	7+00.00 TO 9+00.00 LT
553	7+00.00 TO 9+00.00 RT
384	MAIN STREET 309+75.00 TO 310+75.00 RT
59030	TOTAL

SEEDING, CLASS 1

ACRE	LOCATION
0.98	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
0.87	61+00.00 TO 79+00.00 RT
1.28	79+00.00 TO 109+00.00 LT
1.88	79+00.00 TO 114+00.00 RT
0.03	TOWER ROAD 7+00.00 TO 9+00.00 LT
0.05	7+00.00 TO 9+00.00 RT
0.05	MAIN STREET 309+75.00 TO 310+75.00 RT
5.14	TOTAL

SEEDING, CLASS 2

ACRE	LOCATION
0.87	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
0.36	61+00.00 TO 79+00.00 RT
1.20	79+00.00 TO 109+00.00 LT
1.22	79+00.00 TO 114+00.00 RT
0.47	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
0.38	79+00.00 TO 85+00.00 LT
1.35	85+00.00 TO 103+00.00 RT
0.41	EAST DETOUR 62+00.00 TO 76+94.50 LT
0.42	WEST DETOUR 98+37.01 TO 113+25.00 RT
0.06	TOWER ROAD 7+00.00 TO 9+00.00 LT
0.07	7+00.00 TO 9+00.00 RT
0.03	MAIN STREET 309+75.00 TO 310+75.00 RT
6.84	TOTAL

NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION
167	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
111	61+00.00 TO 79+00.00 RT
224	79+00.00 TO 109+00.00 LT
279	79+00.00 TO 114+00.00 RT
43	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
35	79+00.00 TO 85+00.00 LT
122	85+00.00 TO 103+00.00 RT
37	EAST DETOUR 62+00.00 TO 76+94.50 LT
38	WEST DETOUR 98+37.01 TO 113+25.00 RT
9	TOWER ROAD 7+00.00 TO 9+00.00 LT
11	7+00.00 TO 9+00.00 RT
8	MAIN STREET 309+75.00 TO 310+75.00 RT
1084	TOTAL

PHOSPHORUS FERTILIZER NUTRIENT

POUND	LOCATION
167	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
111	61+00.00 TO 79+00.00 RT
224	79+00.00 TO 109+00.00 LT
279	79+00.00 TO 114+00.00 RT
43	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
35	79+00.00 TO 85+00.00 LT
122	85+00.00 TO 103+00.00 RT
37	EAST DETOUR 62+00.00 TO 76+94.50 LT
38	WEST DETOUR 98+37.01 TO 113+25.00 RT
9	TOWER ROAD 7+00.00 TO 9+00.00 LT
11	7+00.00 TO 9+00.00 RT
8	MAIN STREET 309+75.00 TO 310+75.00 RT
1084	TOTAL

POTASSIUM FERTILIZER NUTRIENT

POUND	LOCATION
167	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
111	61+00.00 TO 79+00.00 RT
224	79+00.00 TO 109+00.00 LT
279	79+00.00 TO 114+00.00 RT
43	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
35	79+00.00 TO 85+00.00 LT
122	85+00.00 TO 103+00.00 RT
37	EAST DETOUR 62+00.00 TO 76+94.50 LT
38	WEST DETOUR 98+37.01 TO 113+25.00 RT
9	TOWER ROAD 7+00.00 TO 9+00.00 LT
11	7+00.00 TO 9+00.00 RT
8	MAIN STREET 309+75.00 TO 310+75.00 RT
1084	TOTAL

MULCH, METHOD 2

ACRE	LOCATION
1.85	ILLINOIS ROUTE 113 61+00.00 TO 79+00.00 LT
1.23	61+00.00 TO 79+00.00 RT
2.48	79+00.00 TO 109+00.00 LT
3.1	79+00.00 TO 114+00.00 RT
0.47	ILLINOIS ROUTE 113 - OLD PAVEMENT REMOVAL 73+00.00 TO 79+00.00 LT
0.38	79+00.00 TO 85+00.00 LT
1.35	85+00.00 TO 103+00.00 RT
0.41	EAST DETOUR 62+00.00 TO 76+94.50 LT
0.42	WEST DETOUR 98+37.01 TO 113+25.00 RT
0.09	TOWER ROAD 7+00.00 TO 9+00.00 LT
0.12	7+00.00 TO 9+00.00 RT
0.08	MAIN STREET 309+75.00 TO 310+75.00 RT
12.0	TOTAL

EROSION CONTROL BLANKET

SQ YD	LOCATION
18	62+44 43.5' LT
18	62+44 30.5' RT
9	68+24 37.0' RT
9	68+90 37.0' RT
9	84+70 41.0' RT
9	85+10 41.0' RT
19	94+41 48.0' LT
278	94+41 52.0' RT
9	103+78 52.0' RT
9	104+12 52.0' RT
18	104+24 48.5' RT
18	104+32 39.5' LT
12	104+72 38.0' LT
12	105+28 38.0' LT
9	7+27 30.0' LT
9	7+80 30.0' LT
465	TOTAL

SODDING, SALT TOLERANT

SQ YD	LOCATION
755	3+96.28 TO 7+18.31 LT
648	3+96.28 TO 7+18.31 RT
1403	TOTAL

SUPPLEMENTAL WATERING

UNIT	LOCATION	
6.8	3+96.28 TO 7+18.31 LT	3 APPLICATIONS
5.9	3+96.28 TO 7+18.31 RT	3 APPLICATIONS
12.7	TOTAL	

DATE: _____
 BY: _____
 PLAN NO. _____
 SURVEYED _____
 ALIGNED _____
 CHECKED _____
 NOTE BOOK NO. _____
 PLOTTED _____
 FILE NAME _____

DATE: _____
 BY: _____
 PROFILE NO. _____
 SURVEYED _____
 GRADES CHECKED _____
 NOTED _____
 STRUCTURE NOTATION SHOWN _____

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAU 6194 (ILLINOIS ROUTE 113)
 SCHEDULE OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____