

END SECTIONS 18"

EACH	LOCATION			
2	68+57	37'	RT	
2	84+89.50	41'	RT	
2	103+95	52'	RT	
2	7+52	30'	LT	
8	TOTAL			

END SECTIONS 24"

EACH	LOCATION			
2	105+00	38'	LT	
2	TOTAL			

PRECAST REINFORCED CONCRETE FLARED END SECTION 24"

EACH	LOCATION			
1	75+50	52'	LT	
1	75+50	46'	RT	
2	TOTAL			

PRECAST REINFORCED CONCRETE FLARED END SECTION 30"

EACH	LOCATION			
1	104+23	59.2'	RT	
1	TOTAL			

CONCRETE HEADWALLS FOR PIPE DRAINS

EACH	LOCATION			
1	91+25	31'	LT	
1	91+25	31'	RT	
1	94+00	31'	LT	
1	94+00	32'	RT	
4	TOTAL			

PIPE UNDERDRAINS, 4"

FOOT	LOCATION			
275	88+50 TO 91+25		LT	
275	88+50 TO 91+25		RT	
275	91+25 TO 94+00		LT	
275	91+25 TO 94+00		RT	
1100	TOTAL			

PIPE UNDERDRAINS 4" (SPECIAL)

FOOT	LOCATION			
15	91+25		LT	
15	91+25		RT	
15	94+00		LT	
16	94+00		RT	
61	TOTAL			

ISLAND PAVEMENT (SPECIAL)

SQ YD	LOCATION			
61	70+30.38 TO 78+90.45	LT		INTERSECTION ISLAND
61	TOTAL			

STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION			
237.5	60+35.00 TO 62+72.50		RT	
237.5	TOTAL			

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION			
1	59+85.00 TO 60+35.00		RT	
1	TOTAL			

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)

EACH	LOCATION			
1	62+72.50 TO 63+22.50		RT	
1	TOTAL			

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

EACH	LOCATION				
1	60+17.39	58.77'	LT		
1	60+36.64	75.00'	LT		
1	62+00.00	60.00'	RT		
1	63+00.00	75.00'	LT		
1	64+00.00	60.00'	LT		
1	68+00.00	60.00'	LT		
1	70+00.00	60.00'	RT		
1	70+12.93	80.00'	LT		
1	72+00.00	65.00'	RT		
1	75+49.08	80.00'	LT		
1	75+49.08	65.00'	RT		
1	76+00.00	75.00'	LT		
1	77+00.00	60.00'	RT		
1	78+00.00	75.00'	LT		
1	80+00.00	60.00'	LT		
1	90+00.00	60.00'	LT		
1	92+00.00	75.00'	LT		
1	93+00.00	60.00'	RT		
1	94+00.00	65.00'	RT		
1	95+00.64	75.00'	LT		
1	97+00.00	65.00'	RT		
1	98+00.00	60.00'	LT		
1	98+00.00	60.00'	RT		
1	102+00.00	60.00'	LT		
1	103+00.00	65.00'	LT		
1	105+16.38	65.00'	LT		
1	105+16.38	60.00'	RT		
1	109+00.00	33.00'	RT		
1	110+00.00	33.00'	LT		
1	6+45.63	30.88'	RT	TOWER	
1	6+74.38	60.55'	RT	TOWER	
1	7+22.98	120.67'	LT	TOWER	
1	7+44.07	72.72'	RT	TOWER	
1	7+48.68	57.73'	RT	TOWER	
1	7+71.16	37.49'	LT	TOWER	
1	7+81.78	110.67'	LT	TOWER	
1	8+75.00	40.00'	LT	TOWER	
1	9+00.00	50.00'	RT	TOWER	
38	TOTAL				

PERMANENT SURVEY MARKERS, TYPE I

EACH	LOCATION				
1	70+12.93		PC		
1	75+49.08		PT		
1	79+05.49		INT		
1	95+00.64		PC		
1	105+16.38		PT		
1	6+69.84		PC	TOWER ROAD	
1	8+14.18		PT	TOWER ROAD	
7	TOTAL				

SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION				
580	ILLINOIS 113				
195	33+00 TO 62+00 CL	CENTERLINE YELLOW		2 APPLICATIONS	
38	62+00 TO 88+50 CL	CENTERLINE YELLOW		3 APPLICATIONS	
44	106+75 TO 108+00 CL	CENTERLINE YELLOW		3 APPLICATIONS	
44	108+00 TO 110+20 CL	CENTERLINE YELLOW		2 APPLICATIONS	
97	TOWER ROAD				
954	3+96.28 TO 7+18.31 CL	CENTERLINE YELLOW		3 APPLICATIONS	
954	TOTAL				

TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION			
46.8	76+65.00 TO 78+65.00	LEFT-TURN LANE		
46.8	TOTAL			

TEMPORARY PAVEMENT MARKING - LINE 4"

FOOT	LOCATION				
	ILLINOIS ROUTE 113				
260	33+00 TO 35+60	RT	CENTERLINE	SINGLE YELLOW	
260	33+00 TO 35+60	LT	EDGE LINE	WHITE	
260	33+00 TO 35+60	RT	EDGE LINE	WHITE	
1320	35+60 TO 48+80	LT	EDGE LINE	WHITE	
1320	35+60 TO 48+80	RT	EDGE LINE	WHITE	
792	48+80 TO 56+72	LT	CENTERLINE	SINGLE YELLOW	
792	48+80 TO 56+72	LT	EDGE LINE	WHITE	
792	48+80 TO 56+72	RT	EDGE LINE	WHITE	
1056	56+72 TO 62+00	CL	CENTERLINE	DOUBLE YELLOW	
528	56+72 TO 62+00	LT	EDGE LINE	WHITE	
528	56+72 TO 62+00	RT	EDGE LINE	WHITE	
1970	62+00 TO 71+85	CL	CENTERLINE	DOUBLE YELLOW	
1467	62+00 TO 76+67	LT	EDGE LINE	WHITE	
4600	62+00 TO 108+00	RT	EDGE LINE	WHITE	
600	71+85 TO 74+85	LT	TURN-LANE	DOUBLE YELLOW	
600	71+85 TO 74+85	RT	TURN-LANE	DOUBLE YELLOW	
360	74+85 TO 78+65	RT/LT	TURN-LANE	DOUBLE YELLOW	
760	74+85 TO 78+65	LT	TURN-LANE	DOUBLE YELLOW	
722	79+74 TO 83+35	LT	MEDIAN	DOUBLE YELLOW	
722	79+74 TO 83+35	RT	MEDIAN	DOUBLE YELLOW	
2796	80+04 TO 108+00	LT	EDGE LINE	WHITE	
4930	83+35 TO 108+00	CL	CENTERLINE	DOUBLE YELLOW	
440	108+00 TO 110+20	CL	CENTERLINE	DOUBLE YELLOW	
220	108+00 TO 110+20	LT	EDGE LINE	WHITE	
220	108+00 TO 110+20	RT	EDGE LINE	WHITE	
	TOWER ROAD				
1136	3+96.28 TO 9+64.36	CL	CENTERLINE	DOUBLE YELLOW	
	MAIN STREET				
94	310+08 TO 310+55	CL	CENTERLINE	DOUBLE YELLOW	
29545	TOTAL				

TEMPORARY PAVEMENT MARKING - LINE 6"

FOOT	LOCATION				
65	33+00 TO 35+60	CL	SKIP-DASH	YELLOW	
330	35+60 TO 48+80	CL	SKIP-DASH	YELLOW	
198	48+80 TO 56+72	CL	SKIP-DASH	YELLOW	
593	TOTAL				

TEMPORARY PAVEMENT MARKING - LINE 8"

FOOT	LOCATION				
45	74+85 TO 76+65	RT	SKIP-DASH	WHITE	
200	76+65 TO 78+65	RT	LANE LINE	WHITE	
130	78+30.38 TO 78+90.45	LT	ISLAND	WHITE	
375	TOTAL				

TEMPORARY PAVEMENT MARKING - LINE 12"

FOOT	LOCATION				
110	71+85 TO 76+65	LT/RT	MEDIAN DIAGONALS	YELLOW	
53	78+30.38 TO 78+90.45	LT	ISLAND DIAGONALS	WHITE	
88	79+74.69 TO 83+35	LT/RT	MEDIAN DIAGONALS	YELLOW	
251	TOTAL				

TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION					
	TOWER ROAD					
24	9+58.87	31.15'	RT	STOP BAR	WHITE	
15	9+64.36	0'	RT	STOP BAR	WHITE	
	MAIN STREET					
12	310+55.14	0'	RT	STOP BAR	WHITE	
	INDIAN TRAIL					
28	10+45.00	7.5'	RT	STOP BAR	WHITE	
79	TOTAL					

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU 6194 (ILLINOIS ROUTE 113)
SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____

PLAN SURVEYED _____
 CHECKED _____
 DATE _____
 NO. _____

PROFILE SURVEYED _____
 CHECKED _____
 DATE _____
 NO. _____

*****DATE*****