

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(18, 19)RS-3	IRROQUOIS	28	9
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

CONTRACT #66417

SIDEROAD AND ENTRANCE SCHEDULE

STA	SIDE	SIDEROAD OR ENTRANCE	MATERIAL	WIDTH	AREA	BIT SURF REM 1 1/2	BIT SURF REM 3 1/4	INC BIT SURF	BIT MAT'L (PR CT)	AGG (PR CT)	TEMP RAMP	BIT SURF REM BUTT JT	AGG SURF TY B
				FOOT	SQ YD	SQ YD	SQ YD	TON	GAL	TON	SQ YD	SQ YD	TON
2625+51	LT	PE (2390E)	BIT/AGG	14	27			3.4	2.2	0.05			1.0
2625+51	RT	MBTO (2390E)	AGG	25	23			2.9	8.6	0.05			
2640+25	RT	2420 E	BIT	21	113			14.2	9.0	0.23	11.7	46.7	
2644+57	LT	2430 E	BIT	40	176			22.2	14.1	0.35	22.2	88.9	
2684+50	LT	2500 E	BIT	20	110			13.9	8.8	0.22	11.1	44.4	
2684+50	RT	2500 E	BIT	17	100			12.6	8.0	0.2	9.4	37.8	
2731+87	LT	2580 E	BIT	21	113			14.2	9.0	0.23	9.3	9.3	
2731+87	RT	2580 E	BIT	20	110			13.9	8.8	0.22	8.9	8.9	
2791+00	LT	2700 E	BIT	20	110			13.9	8.8	0.22	11.1	44.4	
2791+00	RT	2700 E	BIT	21	113			14.2	9.0	0.23	11.7	46.7	
2830+54	LT	2780 E	BIT	20	110			13.9	8.8	0.22	11.1	44.4	
2841+43	LT	PE W/MBTO	BIT	14	27			3.4	2.2	0.05		6.2	
2843+68	RT	DARROW RD	BIT	20	110			13.9	8.8	0.22	8.9	8.9	
2857+12	LT	2820 E	BIT	24	123			15.5	9.8	0.25	13.3	53.3	
2869+80	LT	PE W/MBTO (2844E)	BIT	20	91			11.5	7.3	0.2		8.9	
2896+94	LT	TR 418	BIT	20	110	110		9.2	8.8	0.22	22.2		
2896+94	RT	TR 416	BIT	20	110	110		9.2	8.8	0.22	22.2		
2929+24.58	LT	US 52 (110' BK FROM EOP)	BIT	40	532		532	96.8	42.6	1.06	44.4		
2929+34.58	RT	2960 E	BIT	40	176		176	32.0	14.1	0.35	44.4		
2949+96	LT	3000 E (TR 442)	BIT	20	110	110		9.2	8.8	0.22	22.2		
2949+96	RT	3000 E (TR 442A)	BIT	40	176	176		14.8	14.1	0.35	44.4		
3012+30	LT	REST AREA	BIT	40	176	176		14.8	14.1	0.35	44.4		
3017+10	LT	REST AREA	BIT	40	176	176		14.8	14.1	0.35	44.4		
3025+74	LT	WEIGH STATION	BIT	36	163	163		13.7	13.0	0.33	40.0		
3031+14	LT	WEIGH STATION	BIT	40	176	176		14.8	14.1	0.35	44.4		
3033+37	LT	3180 E (TR 522)	NO WORK										
3035+47	LT	CE	NO WORK										
3036+47	LT	CE	NO WORK										
3037+81	LT	3190 E (TR 523)	NO WORK										
3041+00	LT	PE 3198 E	NO WORK										
3042+53	RT	3200 E	NO WORK										
3042+55	LT	3200 E	NO WORK										
TOTAL						1197	708	412.9	275.7	6.74	501.7	448.8	1

CLASS A PATCHING, 7 IN.

STATION	L	W	TY II	TY III	TY IV	TIE BARS	PATCH REINF	SAW CUTS
	FOOT	FOOT	SQ YD	SQ YD	SQ YD	EACH	SQ YD	FOOT
EB DRIVE LANE								
2912+05	10	12	13.3				13.3	68
2922+30	6	12	8.0				8.0	60
2925+90	6	12	8.0				8.0	60
2935+50	6	12	8.0				8.0	60
2943+00	6	12	8.0				8.0	60
2946+00	8	12	10.7				10.7	64
2953+98	12	12		16.0			16.0	72
2965+25	8	12	10.7				10.7	64
2972+00	6	12	8.0				8.0	60
2981+00	6	12	8.0				8.0	60
2983+25	8	12	10.7				10.7	64
2991+00	6	12	8.0				8.0	60
2995+90	12	12		16.0			16.0	72
WB DRIVE LANE								
2917+00	6	12	8.0				8.0	60
2932+50	15	12		20.0			20.0	78
2938+50	6	12	8.0				8.0	60
2940+00	6	12	8.0				8.0	60
2949+60	8	12	10.7				10.7	64
2958+30	6	12	8.0				8.0	60
2962+95	8	12	10.7				10.7	64
2968+75	6	12	8.0				8.0	60
2975+00	20	12			26.7	10	26.7	88
2978+50	8	12	10.7				10.7	64
2985+00	6	12	8.0				8.0	60
2988+25	6	12	8.0				8.0	60
TOTAL			189.5	52.0	26.7	10	268.2	1602

OMISSIONS
 SN 038-0037 - 2704+30 TO 2705+76
 KB & S RR - 2820+14.86 TO 2820+22.86
 KB & S RR - 2925+40 TO 2925+49

NOVEMBER 17, 2004
 Fed01804/schedUtes.dgn

SCHEDULES