

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	138-41RS-2	ILLINOIS	10	2
STA.	340+00	TO STA.	407+00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

GENERAL NOTES:

Plan dimensions and details relative to the existing roadway and structure have been taken from existing plans and are subject to nominal construction variations. It shall be the contractor's responsibility to verify such dimensions and details in the field and to make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in the scope of the work, however, the contractor will be paid for the quantity actually furnished at the unit price bid for the work.

The contractor shall be responsible for protecting utility property from construction operations as outlined in Article 107.31 of the Standard Specifications. The "Julie" Number is 1-800-892-0123. A minimum of forty-eight (48) hours advance notice is required.

The cost of any saw cuts made to complete the work as described in plan details, unless otherwise noted shall not be paid for separately but shall be included in the various pay items involved.

The thickness of bituminous mixtures shown on the plans is the nominal thickness. Deviations from the nominal thickness will be permitted when such deviations occur due to irregularities in the existing surface or base on which the bituminous mixture is placed.

The Engineer will be the sole judge concerning curing time for the various bituminous lifts.

For stabilization, all Type III barricades shall require a minimum of four sand bags per barricade.

Where section or subsection monuments are encountered, the engineer shall be notified before such monuments are removed. The contractor shall protect and carefully preserve all monuments until an authorized surveyor or agent has witnessed or otherwise referenced their location. The contractor shall be responsible for having an authorized surveyor reestablish any section or subsection monuments destroyed by his operations.

Abandoned underground utilities that conflict with construction shall be disposed of outside the limits of the right of way according to Article 202.03 of the Standard Specifications and as directed by the Engineer. This work will not be paid for separately but shall be included in the cost of earth excavation.

Any reference to a standard in these plans shall be interpreted to mean the edition as indicated by the subnumber listed on the index of sheets or the copy of the standard included in these plans.

The following rates of application have been used in calculation plan quantities:

Bituminous Mat Prime Coat	0.08	Gal/ Sq Yd or
Aggregate Prime Coat	0.002	Tons/Sq Yd
Bituminous Resurfacing	112	Lbs/Sq Yd/In
Short Term Pavement Marking	10	Ft/100 ft of application
Mix for Cracks, JTS & Flgwys	0.0003	Tons/Sq Yd
Level Binder (Hand Method)	0.0005	Tons/Sq Yd

	POLYMERIZED BITUMINOUS CONCRETE SURFACE CSE. SUPERPAVE
PG GRADE	SBS PG70-22
MAX % RAP ALLOWABLE	0%
DESIGN AIR VOIDS	4.0% @ N90
MIXTURE COMPOSITION	IL 12.5 OR IL 9.5
FRICTION AGGREGATE	MIXTURE D
PLANT CONTROL LIMITS	CLASS I
DENSITY CONTROL METHOD	CORES/ CORRELATION

DATE: 12-21-04

PREPARED BY: *Bruce A. Ancker*
DISTRICT OPERATIONS ENGINEER

EXAMINED BY: *Hubert J. [Signature]*
DISTRICT CONSTRUCTION ENGINEER

T.P. Samchen
DISTRICT STUDIES & PLANS ENGINEER

Kenneth R. [Signature]
DISTRICT MATERIALS ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: VERT. DRAWN BY RW
 HORIZ. CHECKED BY
 DATE 10/07/04

DATE = 10/07/04
FILE NAME = C:\meir\05\cm313\details.dgn