

F&S SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2466	IOT	MCLEAN	13	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66530

SUMMARY OF QUANTITIES				
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		TOTAL QUANTITY
			C000	
		UNIT		
20200100	EARTH EXCAVATION	CU YD		731
20800150	TRENCH BACKFILL	CU YD		14
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT		100
25000200	SEEDING, CLASS 2	ACRE		0.6
25000400	NITROGEN FERTILIZER NUTRIENT	POUND		51
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND		51
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND		51
25100630	EROSION CONTROL BLANKET	SQ YD		2762
28000300	TEMPORARY DITCH CHECKS	EACH		3
28100107	STONE RIPRAP, CLASS A4	SQ YD		20
28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD		20
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON		5
54207171	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	FOOT		96
50105200	REMOVE EXISTING CULVERTS	EACH		1
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH		2
55101100	STORM SEWER REMOVAL 21"	FOOT		33
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH		3
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH		2
67100100	MOBILIZATION	L SUM		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT.  
HORIZ.

DATE

DRAWN BY

CHECKED BY