

F.A.S. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2466	10T	MCLEAN	13	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 66530				

REMOVAL ITEMS		
LOCATION	REMOVE EXISTING CULVERTS	STORM SEWER REMOVAL 21"
	EACH	FEET
STA. 76+61.43, RT.	1	
STA. 85+05, RT.		33
STA. 82+55.20, RT.		
TOTALS	1	33

EARTH EXCAVATION					
1 LOCATION	2	3	4	5	6
	DISTANCE FEET	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
STA. 75+60.00 TO STA. 77+00.00	140	55.0	41.3	111.6	-70.4
STA. 77+00.00 TO STA. 79+00.00	200	281.8	211.4	63.1	148.3
STA. 79+00.00 TO STA. 81+00.00	200	254.8	191.1	0.0	191.1
STA. 81+00.00 TO STA. 82+60.00	160	139.8	104.9	0.0	104.9
TOTALS		731.4	548.6	174.7	373.9

COLUMN 4 = EARTH EXCAVATION ADJUSTED USING SHRINKAGE FACTOR OF 25%

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	
LOCATION	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)
	EACH
STA. 41.06, 30.4' RT.	1
STA. 79+94.32, 31' RT	1
STA. 82+03.36, 26.47'	1
TOTALS	3

SEEDING						
LOCATION	DISTANCE BETWEEN STATIONS	SEEDING CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	EROSION CONTROL BLANKET
	FEET	ACRE	POUND	POUND	POUND	SQ YD
STA. 75+60.00 TO STA. 77+00.00	140	0.13	11.3	11.3	11.3	613.3
STA. 77+00.00 TO STA. 79+00.00	200	0.18	16.6	16.6	16.6	890.4
STA. 79+00.00 TO STA. 81+00.00	200	0.16	14.8	14.8	14.8	789.5
STA. 81+00.00 TO STA. 82+60.00	160	0.10	8.7	8.7	8.7	469.3
TOTALS		0.6	51.4	51.4	51.4	2762.4

DRAINAGE SCHEDULE		
LOCATION	PIPE CULV., TYPE 1 REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	PRC FLARED END SECTION ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"
	FEET	EACH
STA. 76+61.43, RT.	96	2
TOTALS	96	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DATE HORIZ. DATE

DRAWN BY _____
CHECKED BY _____