

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(53-3)I	LIVINGSTON	14	4
STA. 331+64		TO STA. 338+18		
FED. ROAD DIST. NO. - ILLINOIS				

SUMMARY OF QUANTITIES

1000

CONSTRUCTION CODE:

RURAL
100% STATE
TOTAL
QUANTITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	42
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2430
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	779
70400100	TEMPORARY CONCRETE BARRIER	FOOT	950
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	940
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1280
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	320
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32
78300100	PAVEMENT MARKING REMOVAL	SQ FT	802
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAINS REMOVAL	EACH	4
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
XZ191300	AGGREGATE SUBGRADE	CU YD	1587
* Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	EACH	1
* Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	EACH	1
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	1493

*SFTY-3N

PLOT DATE : SEPTEMBER 21, 2004
 FILE NAME : c:\msd57\cm327\06040114.dgn

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY RW
 HORIZ. CHECKED BY
 DATE 09/21/04