

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	04 BRIDGE REP.	PEORIA	14	6
STA. 409+99.02		TO STA. 414+72.02		
FED. ROAD DIST. NO. 4		ILLINOIS FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

## PAVEMENT MARKING TAPE, TYPE III, 4"

JOBSITE BRIDGE DECK = 3330 FOOT

## CONCRETE SUPERSTRUCTURE

PARAPET WALLS & PIER 3 = 8.7 CU. YD.  
 N. ABUT. & DECK STA. 409+99.35 = 7.15 CU. YD.  
 S. ABUT. & DECK STA. 413+50.23 = 7.15 CU. YD.  
 TOTAL = 23.0 CU. YD.

## WATERPROOFING MEMBRANE SYSTEM

JOBSITE BRIDGE DECK = 1516 SQ. YDS.

## BIT. SURF. CRSE, SUPERPAVE, N50, 1 3/8"

JOBSITE BRIDGE DECK = 119 TON

## ENGINEERS FIELD OFFICE, TYPE A

JOBSITE = 2.0 CAL. MO.

## MOBILIZATION

JOBSITE = 1.0 LSUM

## THERMOPLASTIC PAVEMENT MARKING LINE, 4"

JOBSITE BRIDGE DECK = 1440 FOOT

## THERMOPLASTIC PAVEMENT MARKING LINE, 6"

JOBSITE BRIDGE DECK = 36 FOOT

PLT DATE = 01/13/04  
 FILE NAME = 011114  
 PLOT SCALE = 1/8"=1'-0"  
 REFERENCE = 011114

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULE OF QUANTITIES

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE: 01-13-2004

DRAWN BY: CEJ  
 CHECKED BY: \_\_\_\_\_