

SUMMARY OF QUANTITIES

CONTRACT NO. 70028
 •(15,18-20)RS-2&(15-22)RS-2
 •COLES & CUMBERLAND

LOCATION OF WORK: CUMBERLAND

COLES

FM STA. 119+16.79 TO STA. 286+88.78 I-57 ROADWAY RURAL 4 LANE 90% FED 10% STATE 1000	FM STA. 286+88.78 TO STA. 340+00.00 & FM STA. 482+00.00 TO STA. 691+79.69 & FM STA. 815+87.69 TO STA. 841+07.00 I-57 ROADWAY RURAL 4 LANE 90% FED 10% STATE 1000	FM STA. 691+79.69 TO STA. 815+87.69 I-57 ROADWAY URBAN 4 LANE 90% FED 10% STATE 1000
--------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------

RURAL
 I-57
 BRIDGE
 S. N. 015-0003
 S. N. 015-0004
 4 LANE
 90% FED
 10% STATE
 SAFETY-2A

I-57
 BRIDGE
 S. N. 015-0032
 URBAN
 2 LANE
 90% FED
 10% STATE
 SAFETY-2A

CODE NO.	PAY ITEM	UNIT	QUANTITY	CONSTRUCTION TYPE CODE:	10% STATE 1000	10% STATE 1000	10% STATE 1000	10% STATE 1000
X4409525	BITUMINOUS SURFACE REMOVAL 6 1/4"	SQ. YD.	58,567.0		44,404.0	14,163.0		
X4420054	CLASS A PATCHES, TYPE IV, 11 1/4 INCH	SQ. YD.	93.0				93.0	
X4420410	CLASS D PATCHES, TYPE II, 14 3/4 INCH	SQ. YD.	7.0		7.0			
X4420155	CLASS D PATCHES, TYPE III, 15 1/4 INCH	SQ. YD.	18.0		18.0			
X4420156	CLASS D PATCHES, TYPE II, 15 1/4 INCH	SQ. YD.	12.0		12.0			
6010076	SHOULDER REMOVAL AND REPLACEMENT 11"	FOOT	136,869.0		112,778.3	24,090.7		
20200100	EARTH EXCAVATION	CU. YD.	440.0			440.0		
20400800	FURNISHED EXCAVATION	CU. YD.	5,835.0		1,336.4	2,727.0	1,771.6	
25000200	SEEDING, CLASS 2	ACRE	4.0		0.72	1.84	1.39	0.05
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	360.0		64.8	166.0	124.7	4.5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	360.0		64.8	166.0	124.7	4.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	360.0		64.8	166.0	124.7	4.5
25100120	MULCH METHOD 2	TON	8.0		1.4	3.7	2.8	0.1
25100670	EROSION CONTROL BLANKET	SQ. YD.	1,164.0		999.0	165.0	356.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400.0		72.0	184.4	138.6	5.0
28000500	INLET AND PIPE PROTECTION	EACH	6.0		3.0	2.0	1.0	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ. YD.	1,513.0			1,513.0		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	64.0			43.0	21.0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19,254.0		5,526.0	9,669.0	4,050.0	
40600105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GALLON	32,902.0		9,465.0	16,458.0	6,979.0	
40600300	AGGREGATE (PRIME COAT)	TON	1,043.0		300.0	513.0	230.0	
40600895	CONSTRUCT TEST STRIP	EACH	2.0		1.0	1.0		
40600980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ. YD.	14,118.0		3,282.0	5,835.4	5,000.6	
40600990	TEMPORARY RAMP	SQ. YD.	3,920.0		604.5	2,276.7	1,038.8	
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	107.0		13.5	66.5	27.0	
44000006	BITUMINOUS SURFACE REMOVAL, 1 1/2"	SQ. YD.	127,681.0		96,836.0	30,845.0		
44000010	BITUMINOUS SURFACE REMOVAL, 3 1/2"	SQ. YD.	265.0			265.0		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	3,354.0			2,105.7	1,248.3	
44000035	BITUMINOUS SURFACE REMOVAL	SQ. YD.	391.0			260.6	130.4	
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ. YD.	444.0			321.0	123.0	
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ. YD.	84.0			52.0	32.0	
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ. YD.	80.0			80.0		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ. YD.	53.0			53.0		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ. YD.	20.0		20.0			
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ. YD.	32.0		32.0			
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ. YD.	60.0		60.0			
44213000	PATCHING REINFORCEMENT	SQ. YD.	1,289.0			805.7	483.3	
44213200	SAW CUTS	FOOT	8,734.00			6,042.0	2,692.0	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7,509.0		1,961.0	3,959.0	1,589.0	
48202000	BITUMINOUS SHOULDERS, SUPERPAVE	TON	19,161.0		4,760.0	10,558.0	3,843.0	

• SPECIALTY ITEMS

REVISED
 2-22-05