

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57		**	76	24

CONTRACT NO. 70028
 *(15,18-20)RS-2&(15-22)RS-2
 **COLES & CUMBERLAND

SCHEDULE OF QUANTITIES

CLASS 'B' PATCHES

	STATION	DIRECTION	LOCATION	LENGTH (FT.)	WIDTH (FT.)	PATCH AREA				DOWEL BARS (EACH)	SAW CUT (FT.)
						TYPE I (SQ. YD)	TYPE II (SQ. YD)	TYPE III (SQ. YD)	TYPE IV (SQ. YD)		
COLES CO.	14+75+/-	NB	RAMP B	6	16	0.0	10.7	0.0	0.0	28	60.0
	510+39	NB	RAMP A	6	16	0.0	10.7	0.0	0.0	28	60.0
US 45 INTER.	12+25+/-	SB	RAMP D	6	16	0.0	10.7	0.0	0.0	28	60.0
	62+14	SB	RAMP C	6	16	0.0	10.7	0.0	0.0	28	60.0
MATTOON	68+91	SB	RAMP C	6	16	0.0	10.7	0.0	0.0	28	60.0
CLASS 'B' PATCH TOTAL						0.0	53.3	0.0	0.0	140	300.0

CLASS 'D' PATCHES

	STATION	DIRECTION	LOCATION	LENGTH (FT.)	WIDTH (FT.)	DEPTH (IN.)	PATCH AREA				
							TYPE I (SQ. YD)	TYPE II (SQ. YD)	TYPE III (SQ. YD)	TYPE IV (SQ. YD)	
CUMB. CO.	119+75	NB	DL	12	12	10.0	0.0	0.0	16.0	0.0	
	120+00	NB	DL	5	12	10.0	0.0	6.7	0.0	0.0	
	120+00	NB	PL	5	12	14.75	0.0	6.7	0.0	0.0	
	250+00	NB	DL	25	12	10.0	0.0	0.0	0.0	33.3	
	252+38	NB	DL	10	12	10.0	0.0	13.3	0.0	0.0	
	250+22	SB	DL	20	12	10.0	0.0	0.0	0.0	26.7	
	252+55	SB	DL	12	12	10.0	0.0	0.0	16.0	0.0	
US 45 INT.	17+76	SB	RAMP B	6	18	15.25	0.0	12.0	0.0	0.0	
NEOGA	17+95	SB	RAMP B	9	18	15.25	0.0	0.0	18.0	0.0	
CLASS 'D' PATCH TOTAL							0.0	38.7	50.0	60.0	