

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709		CHAMPAIGN	64	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		• 113RS-6 & (113BR-2)I CONTRACT NO. 70181		

SUMMARY OF QUANTITIES (Cont'd)

LOCATION OF WORK:

FAP 709 (US ROUTE 136)
SECTION (113RS-6) & (113BR-2) I
CHAMPAIGN COUNTY

CONSTRUCTION TYPE CODE:

FAP 709 (US 136)
URBAN
STA. 105+00
TO
STA. 141+00
80% FED
20% STATE
1000
QUANTITY

FAP 709 (US 136)
RURAL
STA. 141+00
TO
STA. 423+00
80% FED
20% STATE
1000
QUANTITY

RURAL
FAP 709 (US 136)
B-SMART SN 010-0257
STA. 299+49.5
TO
STA. 299+98.50
80% FED
20% STATE
SFTY-2A
QUANTITY

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>URBAN QUANTITY</u>	<u>RURAL QUANTITY</u>	<u>QUANTITY</u>
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	19,720.0	19720.0	0.0	0.0
44000025	BITUMINOUS SURFACE REMOVAL (SPECIAL)	SQ YD	4,868.0	633.0	4235.0	0.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	361.0	0.0	361.0	0.0
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	168.0	0.0	0.0	168.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	158.0	0.0	158.0	0.0
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	74.0	0.0	74.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,814.0	0.0	4814.0	0.0
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	350.0	0.0	350.0	0.0
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	537.0	0.0	537.0	0.0
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	168.0	0.0	0.0	168.0
60260100	INLETS TO BE ADJUSTED	EACH	18.0	18.0	0.0	0.0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10.0	9.0	1.0	0.0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	4.5	0.0	4.5	0.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	346.0	0.0	346.0	0.0