

SCHEDULE OF QUANTITIES

CLARK COUNTY

BITUMINOUS MATERIALS (COVER & SEAL COATS) - 40300300

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (GAL)
503+57.02		574+75.00 (BK)	7,118.00	24.00	3,796.27
575+25.00 (AH)		593+60.00	1,835.00	24.00	978.67
595+52.00		615+02.00 (BK)	1,950.00	24.00	1,040.00
614+52.00 (AH)		656+61.00	4,209.00	24.00	2,244.80
TOTAL =					8,059.8 (GAL)

SEAL COAT AGGREGATE - 40300600

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (TONS)
503+57.02		574+75.00 (BK)	7,118.00	24.00	189.81
575+25.00 (AH)		593+60.00	1,835.00	24.00	48.93
595+52.00		615+02.00 (BK)	1,950.00	24.00	52.00
614+52.00 (AH)		656+61.00	4,209.00	24.00	112.24
TOTAL =					403 (TONS)

MOBILIZATION - 67100100

TOTAL = 0.15
(L. SUM)

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 - 70100460

TOTAL = 0.15
(L. SUM)

TEMPORARY PAINT PAVEMENT MARKING LINE 4" - 70300625

STATION	TO	STATION	LENGTH (FT)
503+57.02		574+75.00 (BK)	7,118.00
575+25.00 (AH)		593+60.00	1,835.00
595+52.00		615+02.00 (BK)	1,950.00
614+52.00 (AH)		656+61.00	4,209.00

TOTAL = 15,112.00
(FT)

SOLID WHITE 4"	15,112 X 30,	224.00
DASH YELLOW 4"	15,112 X 7,	556.00
SOLID YELLOW 4"	15,112 X 3,	022.40

TOTAL = 40,802
(FT)

PAINT PAVEMENT MARKING LINE 4" - 78001110

STATION	TO	STATION	LENGTH (FT)
503+57.02		574+75.00 (BK)	7,118.00
575+25.00 (AH)		593+60.00	1,835.00
595+52.00		615+02.00 (BK)	1,950.00
614+52.00 (AH)		656+61.00	4,209.00

TOTAL = 15,112.00
(FT)

SOLID WHITE 4"	15,112 X 30,	224.00
DASH YELLOW 4"	15,112 X 7,	556.00
SOLID YELLOW 4"	15,112 X 3,	022.40

TOTAL = 40,802
(FT)

COLES COUNTY

BITUMINOUS MATERIALS (COVER & SEAL COATS) - 40300300

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (GAL)
656+61.00		846+80.67	19,019.67	24.00	10,143.82
847+85.33		881+41.00	3,355.67	24.00	1,789.69
TOTAL =					11,933.6 (GAL)

SEAL COAT AGGREGATE - 40300600

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (TONS)
656+61.00		846+80.67	19019.67	24.00	507.19
847+85.33		881+41.00	3355.67	24.00	89.48
TOTAL =					596.60 (TONS)

MOBILIZATION - 67100100

TOTAL = 0.15
(L. SUM)

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 - 70100460

TOTAL = 0.15
(L. SUM)

TEMPORARY PAINT PAVEMENT MARKING LINE 4" - 70300625

STATION	TO	STATION	LENGTH (FT)
656+61.00		846+80.67	19,019.67
847+85.33		881+41.00	3,355.67
TOTAL =			22,375.34 (FT)

SOLID WHITE 4"	22,375.34 X 44,	750.68
DASH YELLOW 4"	22,375.34 X 11,	187.67
SOLID YELLOW 4"	22,375.34 X 4,	475.07

TOTAL = 60,414
(FT)

PAINT PAVEMENT MARKING LINE 4" - 78001110

STATION	TO	STATION	LENGTH (FT)
656+61.00		846+80.67	19,019.67
847+85.33		881+41.00	3,355.67
TOTAL =			22,375.34 (FT)

SOLID WHITE 4"	22,375.34 X 44,	750.68
DASH YELLOW 4"	22,375.34 X 11,	187.67
SOLID YELLOW 4"	22,375.34 X 4,	475.07

TOTAL = 60,414