

SCHEDULE OF QUANTITIES

CUMBERLAND COUNTY

BITUMINOUS MATERIALS (COVER & SEAL COATS) - 40300300

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (GAL)
105+00.00		486+20.00	7,491.70	24.00	3,995.57
180+63.00		452+64.80	27,201.80	24.00	14,507.63
453+72.50		486+20.00	3,247.50	24.00	1,732.00
TOTAL =					20,235.0 (GAL)

SEAL COAT AGGREGATE - 40300600

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (TONS)
105+00.00		486+20.00	7,491.70	24.00	199.78
180+63.00		452+64.80	27,201.80	24.00	725.38
453+72.50		486+20.00	3,247.50	24.00	86.60
TOTAL =					1,011.80 (TONS)

MOBILIZATION - 67100100

TOTAL = 0.30
(L. SUM)

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 - 70100460

TOTAL = 0.30
(L. SUM)

TEMPORARY PAINT PAVEMENT MARKING LINE 4" - 70300625

STATION	TO	STATION	LENGTH (FT)
105+00.00		486+20.00	7,491.70
180+63.00		452+64.80	27,201.80
453+72.50		486+20.00	3,247.50
TOTAL =			37,941.00 (FT)

SOLID WHITE 4" 37,941 X 75,882.00
DASH YELLOW 4" 37,941 X 18,970.50
SOLID YELLOW 4" 37,941 X 18,970.50

TOTAL = 113,823 (FT)

PAINT PAVEMENT MARKING LINE 4" - 78001110

STATION	TO	STATION	LENGTH (FT)
105+00.00		486+20.00	7,491.70
180+63.00		452+64.80	27,201.80
453+72.50		486+20.00	3,247.50
TOTAL =			37,941.00 (FT)

SOLID WHITE 4" 37,941 X 75,882.00
DASH YELLOW 4" 37,941 X 18,970.50
SOLID YELLOW 4" 37,941 X 18,970.50

TOTAL = 113,823 (FT)

MOULTRIE COUNTY

BITUMINOUS MATERIALS (COVER & SEAL COATS) - 40300300

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (GAL)
1+29.80		44+60.18	4,330.38	24.00	2,309.54
45+77.72		66+46.45	2,068.73	24.00	1,103.32
67+56.21		154+16.12	8,659.91	24.00	4,618.62
155+33.66		172+71.41	1,737.75	24.00	926.80
174+51.72		227+31.10	5,279.38	24.00	2,815.67
228+36.74		302+42.96	7,406.22	24.00	3,949.98
302+56.05		432+13.40	12,957.35	24.00	6,910.59
TOTAL =					22,634.6 (GAL)

SEAL COAT AGGREGATE - 40300600

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	QUANTITY (TONS)
1+29.80		44+60.18	4,330.38	24.00	115.48
45+77.72		66+46.45	2,068.73	24.00	55.17
67+56.21		154+16.12	8,659.91	24.00	230.93
155+33.66		172+71.41	1,737.75	24.00	46.34
174+51.72		227+31.10	5,279.38	24.00	140.78
228+36.74		302+42.96	7,406.22	24.00	197.50
302+56.05		432+13.40	12,957.35	24.00	345.53
TOTAL =					1,131.60 (TONS)

MOBILIZATION - 67100100

TOTAL = 0.40
(L. SUM)

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306 - 70100460

TOTAL = 0.40
(L. SUM)

TEMPORARY PAINT PAVEMENT MARKING LINE 4" - 70300625

STATION	TO	STATION	LENGTH (FT)
1+29.80		44+60.18	4,330.38
45+77.72		66+46.45	2,068.73
67+56.21		154+16.12	8,659.91
155+33.66		172+71.41	1,737.75
174+51.72		227+31.10	5,279.38
228+36.74		302+42.96	7,406.22
302+56.05		432+13.40	12,957.35
TOTAL =			42,439.72 (FT)

SOLID WHITE 4" 42,439.72 X 84,879.44
DASH YELLOW 4" 42,439.72 X 21,219.86
SOLID YELLOW 4" 42,439.72 X 8,487.94

TOTAL = 114,587 (FT)

PAINT PAVEMENT MARKING LINE 4" - 78001110

STATION	TO	STATION	LENGTH (FT)
1+29.80		44+60.18	4,330.38
45+77.72		66+46.45	2,068.73
67+56.21		154+16.12	8,659.91
155+33.66		172+71.41	1,737.75
174+51.72		227+31.10	5,279.38
228+36.74		302+42.96	7,406.22
302+56.05		432+13.40	12,957.35
TOTAL =			42,439.72 (FT)

SOLID WHITE 4" 42,439.72 X 84,879.44
DASH YELLOW 4" 42,439.72 X 21,219.86
SOLID YELLOW 4" 42,439.72 X 8,487.94

TOTAL = 114,587 (FT)

RAILROAD PROTECTIVE LIABILITY INSURANCE - Z0048665

TOTAL = 1.00
(L. SUM)