# SCHEDULE OF QUANTITIES

## TABULATION OF PARTIAL DEPTH PATCHING

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 72 | • | •• | 16 | 10 |

CONTRACT NO.70443
• D-5 CONTRACT MAINT. 2005-4
•• MACON & PIATT COUNTIES

MACON COUNTY WESTBOUND
PARTIAL DEPTH PATCHES - 3 1/4 INCH OVERLAY

| BEGIN STATION | END STATION | LANE AND DIRECTION | LENGTH (FT) | WIDTH (FT) | DEPTH (IN) | BIT.SURF.REM. 3 1/4 INCH X4409420 (SQ YD) | PAVEMENT REM (SPECIAL) 44004400 (SQ YD) | BIT. MIX FOR PATCH Z0004800 (TON) |
|---|---|---|---|---|---|---|---|---|
| 430+55.06 | KIRBY | SN058-0087 | | | | | | |
| 497+80.00 | | WBDL | 6.00 | 12.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 514+50.00 | | WBDL | 6.00 | 12.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 516+40.00 | | WBDL | 6.00 | 12.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 524+64.21 | ILLINIWICK | SN058-0089 | | | | | | |
| 599+29.43 | ARGENTA | SN058-0091 | | | | | | |
| 601+30.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 658+67.00 | 658+79.00 | WBDL | 12.00 | 6.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 659+45.00 | 659+57.00 | WBDL | 12.00 | 6.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 691+68.56 | CEMETERY | SN058-0092 | | | | | | |
| 702+40.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 702+60.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 712+00.00 | 712+10.00 | WBDL | 10.00 | 6.00 | 3.25 | 6.7 | 0.0 | 1.2 |
| 715+10.00 | 715+20.00 | WBDL | 10.00 | 6.00 | 3.25 | 6.7 | 0.0 | 1.2 |
| 723+15.00 | 723+35.00 | WBDL | 20.00 | 12.00 | 3.25 | 26.7 | 0.0 | 4.9 |
| 723+60.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 727+30.00 | 727+40.00 | WBDL | 10.00 | 6.00 | 3.25 | 6.7 | 0.0 | 1.2 |
| 732+50.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 738+50.00 | 743+30.00 | WBDL-RAMP | 480.00 | 6.00 | 3.25 | 320.0 | 50.0 | 66.6 |
| 740+00.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 750+00.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 750+20.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 750+33.00 | 750+43.00 | WBDL | 10.00 | 6.00 | 3.25 | 6.7 | 0.0 | 1.2 |
| 750+60.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 750+64.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 751+20.00 | 751+28.00 | WBDL | 8.00 | 6.00 | 3.25 | 5.3 | 0.0 | 1.0 |
| 752+32.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 753+50.00 | 758+14.00 | WBDL-RAMP | 464.00 | 6.00 | 3.25 | 309.3 | 50.0 | 64.7 |
| 764+67.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 770+00.00 | 770+08.00 | WBDL | 8.00 | 6.00 | 3.25 | 5.3 | 0.0 | 1.0 |
| 775+00.00 | 778+70.00 | WBDL-RAMP | 370.00 | 6.00 | 3.25 | 246.7 | 50.0 | 53.3 |
| | REST AREA | | | | | | | |

MACON COUNTY WESTBOUND
PARTIAL DEPTH PATCHES - 3 1/4 INCH OVERLAY

| BEGIN STATION | END STATION | LANE AND DIRECTION | LENGTH (FT) | WIDTH (FT) | DEPTH (IN) | BIT.SURF.REM. 3 1/4 INCH X4409420 (SQ YD) | PAVEMENT REM (SPECIAL) 44004400 (SQ YD) | BIT. MIX FOR PATCH Z0004800 (TON) |
|---|---|---|---|---|---|---|---|---|
| | REST AREA | | | | | | | |
| 783+67.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 785+00.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 787+50.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 788+44.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 792+56.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 799+40.00 | IL48 & RR | SN058-0096 | | | | | | |
| 825+80.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 854+90.00 | SCHOOL | SN058-0097 | | | | | | |
| 910+55.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 911+10.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 911+31.00 | 911+41.00 | WBDL | 10.00 | 16.00 | 3.25 | 17.8 | 0.0 | 3.2 |
| 917+60.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 919+76.00 | | WBDL | 6.00 | 12.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 923+63.00 | 923+75.00 | *WBPL* | 12.00 | 6.00 | 3.25 | 8.0 | 0.0 | 1.5 |
| 924+30.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 925+85.00 | 925+93.00 | WBDL | 8.00 | 6.00 | 3.25 | 5.3 | 0.0 | 1.0 |
| 926+74.00 | | WBDL | 6.00 | 6.00 | 3.25 | 4.0 | 0.0 | 0.7 |
| 932+50.00 | IL48 | SN074-0055 | MACON & PIATT CO. LINE | | | | | |
| MACON COUNTY WESTBOUND PARTIAL DEPTH PATCH - 3 1/4" TOTALS | | | | | | 1111.1 | 150.0 | 227.4 |