

### PAVING SCHEDULE

STATION	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	BIT. CONC. SURF. CSE., SUPER., MIX "D", N70 (TON)	PORTLAND CEMENT CONC. BASE CSE. - 10 1/2" (SQ YDS)	BITUMINOUS SHOULDER SUPERPAVE (TON)	SUBBASE GRAN. MAT. TYPE B (TON)	BITUMINOUS SURFACE REMOVAL - 1 1/2" (SQ YDS)	INCIDENTAL BITUMINOUS SURFACING (TON)
1124 + 31.1 to 1126 + 00.0	0.20	1.00	54	225	19	54	638	
1126 + 00.0 to 1127 + 61.5	0.19	1.00	74	204	17	49	885	
1130 + 18.5 to 1132 + 00.0	0.22	1.25	59	254	21	61	698	
1132 + 00.0 to 1133 + 90.9	0.23	1.50	61	255	22	62	721	
HORSE CREEK ROAD	0.21	1.00		286			286	24
<b>TOTAL</b>	<b>1.05</b>	<b>5.75</b>	<b>223</b>	<b>938</b>	<b>79</b>	<b>226</b>	<b>2942</b>	<b>24</b>

### TEMPORARY WIDENING PAVING SCHEDULE

STATION	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	BIT. CONC. SURF. CSE., SUPER., MIX "D", N70 (TON)	PORTLAND CEMENT CONC. BASE CSE. - 10 1/2" (SQ YDS)	SUBBASE GRAN. MAT. TYPE B (TON)
1126 + 31.2 to 1126 + 90.9	0.025	0.13	7	85	21
1127 + 09.4 to 1128 + 22.9	0.025	0.12	7	83	20
<b>TOTAL</b>	<b>0.050</b>	<b>0.25</b>	<b>14</b>	<b>168</b>	<b>41</b>

### TREE REMOVAL SCHEDULE

STATION	OFFSET LEFT/RIGHT	TREE REMOVAL OVER 15 UNITS DIAMETER (UNITS)	TREE REMOVAL 6 TO 15 UNITS DIAMETER (UNITS)
1127 + 65.0	40' RIGHT	24	6
1127 + 65.0	38' RIGHT	15	
1127 + 65.0	41' RIGHT	24	
1128 + 08.1	38' RIGHT	24	
1129 + 72.6	38' RIGHT	24	
1129 + 72.6	38.5' RIGHT	24	
1129 + 75.5	40' RIGHT	24	6
1129 + 75.5	41' RIGHT	15	
<b>TOTAL</b>		<b>174</b>	<b>12</b>

### EARTHWORK SCHEDULE (SIDEROAD) - FINAL CONSTRUCTION

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
+25.00	to	+50.00	1.1	0.8	16.2	-15.4
+50.00	to	+75.00	12.7	9.5	13.6	-4.1
+50.00	to	+75.00	12.7	9.5	13.6	-4.1
+75.00	to	+100.00	15.1	11.3	7.5	3.8
+75.00	to	+100.00	15.1	11.3	7.5	3.8
+100.00	to	+105.35	1.5	1.1	0.4	0.7
+100.00	to	+105.35	1.5	1.1	0.4	0.7
+105.35	to	+115.59	1.4	1.1	0.0	1.1
+105.35	to	+115.59	1.4	1.1	0.0	1.1
<b>TOTAL =</b>			<b>62.5</b>	<b>46.8</b>	<b>59.2</b>	<b>-12.4</b>
<b>ROUNDED TOTAL =</b>			<b>65</b>	<b>50</b>	<b>60</b>	<b>-15</b>

### EARTHWORK SCHEDULE (SIDEROAD) - STAGE CONSTRUCTION

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
+25.00	to	+50.00	45.6	34.2	0.7	33.5
+50.00	to	+75.00	33.6	25.2	38.9	-13.7
+50.00	to	+75.00	33.6	25.2	38.9	-13.7
+75.00	to	+100.00	6.4	4.8	54.7	-49.9
+75.00	to	+100.00	6.4	4.8	54.7	-49.9
+100.00	to	+105.35	0.7	0.5	6.5	-6.0
+100.00	to	+105.35	0.7	0.5	6.5	-6.0
+105.35	to	+115.59	0.4	0.3	5.8	-5.5
+105.35	to	+115.59	0.4	0.3	5.8	-5.5
<b>TOTAL =</b>			<b>127.8</b>	<b>95.8</b>	<b>212.5</b>	<b>-116.7</b>
<b>ROUNDED TOTAL =</b>			<b>130</b>	<b>100</b>	<b>215</b>	<b>-120</b>

### EARTHWORK SCHEDULE FOR MAINLINE

STA	to	STA	UNADJUSTED EXCAVATION (CU YD)	EXCAVATION ADJUSTED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
1124+31.10	to	1124+43.57	7.1	5.3	0.7	4.6
1124+43.57	to	1124+50.00	3.7	2.8	0.3	2.5
1124+43.57	to	1124+50.00	3.7	2.8	0.3	2.5
1124+50.00	to	1124+75.00	13.0	9.8	7.8	2.0
1124+50.00	to	1124+75.00	13.0	9.8	7.8	2.0
1124+75.00	to	1125+00.00	11.6	8.7	14.4	-5.7
1124+75.00	to	1125+00.00	11.6	8.7	14.4	-5.7
1125+00.00	to	1125+25.00	13.1	9.8	17.1	-7.3
1125+00.00	to	1125+25.00	13.1	9.8	17.1	-7.3
1125+25.00	to	1125+50.00	14.6	11.0	24.5	-13.5
1125+25.00	to	1125+50.00	14.6	11.0	24.5	-13.5
1125+50.00	to	1125+75.00	14.9	11.2	30.7	-19.5
1125+50.00	to	1125+75.00	14.9	11.2	30.7	-19.5
1125+75.00	to	1126+00.00	14.8	11.1	33.2	-22.1
1125+75.00	to	1126+00.00	14.8	11.1	33.2	-22.1
1126+00.00	to	1126+25.00	14.6	11.0	33.2	-22.2
1126+00.00	to	1126+25.00	14.6	11.0	33.2	-22.2
1126+25.00	to	1126+50.00	15.0	11.3	45.6	-34.3
1126+25.00	to	1126+50.00	15.0	11.3	45.6	-34.3
1126+50.00	to	1126+67.45	10.9	8.2	28.4	-20.2
1126+50.00	to	1126+67.45	10.9	8.2	28.4	-20.2
1126+67.45	to	1126+75.00	5.5	4.1	5.8	-1.7
1126+67.45	to	1126+75.00	5.5	4.1	5.8	-1.7
1126+75.00	to	1127+00.00	17.2	12.9	26.1	-13.2
1126+75.00	to	1127+00.00	17.2	12.9	26.1	-13.2
1127+00.00	to	1127+25.00	25.7	19.3	41.4	-22.1
1127+00.00	to	1127+25.00	25.7	19.3	41.4	-22.1
1127+25.00	to	1127+50.00	26.3	19.7	54.5	-34.8
1127+25.00	to	1127+50.00	26.3	19.7	54.5	-34.8
1127+50.00	to	1127+75.00	7.6	5.7	30.9	-25.2
1127+50.00	to	1127+75.00	7.6	5.7	30.9	-25.2
1127+75.00	to	1130+00.00	121.0	98.8	511.4	-420.6
1127+75.00	to	1130+00.00	121.0	98.8	511.4	-420.6
1130+00.00	to	1130+25.00	21.3	16.0	68.0	-52.0
1130+00.00	to	1130+25.00	21.3	16.0	68.0	-52.0
1130+25.00	to	1130+50.00	15.1	11.3	32.3	-21.0
1130+25.00	to	1130+50.00	15.1	11.3	32.3	-21.0
1130+50.00	to	1130+75.00	14.9	11.2	39.3	-28.1
1130+50.00	to	1130+75.00	14.9	11.2	39.3	-28.1
1130+75.00	to	1130+92.95	11.8	8.9	21.3	-12.4
1130+75.00	to	1130+92.95	11.8	8.9	21.3	-12.4
1130+92.95	to	1131+00.00	4.7	3.5	6.0	-2.5
1130+92.95	to	1131+00.00	4.7	3.5	6.0	-2.5
1131+00.00	to	1131+25.00	15.5	11.6	17.9	-6.3
1131+00.00	to	1131+25.00	15.5	11.6	17.9	-6.3
1131+25.00	to	1131+50.00	15.1	11.3	16.6	-5.3
1131+25.00	to	1131+50.00	15.1	11.3	16.6	-5.3
1131+50.00	to	1131+75.00	15.2	11.4	14.7	-3.3
1131+50.00	to	1131+75.00	15.2	11.4	14.7	-3.3
1131+75.00	to	1132+00.00	14.8	11.1	12.2	-1.1
1131+75.00	to	1132+00.00	14.8	11.1	12.2	-1.1
1132+00.00	to	1132+25.00	14.3	10.7	10.0	0.7
1132+00.00	to	1132+25.00	14.3	10.7	10.0	0.7
1132+25.00	to	1132+50.00	14.2	10.7	12.2	-1.5
1132+25.00	to	1132+50.00	14.2	10.7	12.2	-1.5
1132+50.00	to	1132+75.00	14.2	10.7	15.8	-5.1
1132+50.00	to	1132+75.00	14.2	10.7	15.8	-5.1
1132+75.00	to	1133+00.00	14.1	10.6	16.1	-5.5
1132+75.00	to	1133+00.00	14.1	10.6	16.1	-5.5
1133+00.00	to	1133+25.00	14.2	10.7	18.6	-7.9
1133+00.00	to	1133+25.00	14.2	10.7	18.6	-7.9
1133+25.00	to	1133+50.00	14.3	10.7	24.8	-14.1
1133+25.00	to	1133+50.00	14.3	10.7	24.8	-14.1
1133+50.00	to	1133+75.00	14.1	10.6	31.8	-21.2
1133+50.00	to	1133+75.00	14.1	10.6	31.8	-21.2
1133+75.00	to	1133+84.51	5.3	4.0	13.9	-9.9
1133+75.00	to	1133+84.51	5.3	4.0	13.9	-9.9
1133+84.51	to	1133+93.57	2.5	1.9	7.0	-5.1
1133+84.51	to	1133+93.57	2.5	1.9	7.0	-5.1
<b>TOTAL =</b>			<b>1137.3</b>	<b>853.9</b>	<b>2568.3</b>	<b>-1714.4</b>
<b>ROUNDED TOTAL =</b>			<b>1140</b>	<b>855</b>	<b>2570</b>	<b>-1715</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES

FAP ROUTE 312  
SECTION 71BR  
RANDOLPH COUNTY  
SN 079-0048

DRAWN BY:

DATE: \_\_\_\_\_  
BY: \_\_\_\_\_  
PLAN: \_\_\_\_\_  
NO. \_\_\_\_\_  
DATE: \_\_\_\_\_  
BY: \_\_\_\_\_  
PLAN: \_\_\_\_\_  
NO. \_\_\_\_\_