

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
586 60R-2, 37R-1	MADISON	502	4
STA.	TO STA.		
CONTRACT NO.: 76301			

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			URBAN	I000-2A 4 LANE	I000-2A 2 LANE	Y031-1F TRAFFIC SIGNALS	PARKING LANES	X020-2A BOX CULVERT	Y030-1E HIGHWAY
CODE NO	ITEM	UNIT	TOTAL	100% STATE	100% STATE	IL 162 & RIGGIN RD.	50% STATE 50% CITY	SN 060-0403 100% STATE	LIGHTING 100% STATE
40600990	TEMPORARY RAMP	SQ YD	550	418	132				
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.2	1.5	4.7				
40800030	AGGREGATE (PRIME COAT)	TON	13.2	3.8	9.4				
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1036	269	767				
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1156	1156					
42001300	PROTECTIVE COAT	SQ YD	6905	4948	1957				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	188	50	138				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3603	2791	812				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3952	2377	1575				
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	1877		1877				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3975		3975				
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1075		1075				
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16,082	9,676	6,406				
44000100	PAVEMENT REMOVAL	SQ YD	1075	1075					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9864	6150	3714				
44000400	GUTTER REMOVAL	FOOT	3985		3985				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	45		45				
44000600	SIDEWALK REMOVAL	SQ FT	2453	895	1558				
44003100	MEDIAN REMOVAL	SQ FT	72		72				
44004250	PAVED SHOULDER REMOVAL	SQ YD	3083	2826	257				
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	676	322	354				
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	143	62	81				
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	175		175				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	24408	22248	2160				
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	7687		7687				
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	10014		10014				
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1				
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1				
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1		1				
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	5		5				

7/1/2004 1:23:34 PM
 C:\p\projects\10401979\plan\50104400.dgn L:\1-63

Rev. 2-23-05

Rev.