FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
586	60R-2,37R-1	MADISON	502	28
STA.		TO STA.		
CONTRACT NO: 76301				

DRAINAGE STRUCTURE SCHEDULE

POINT	STATION	OFFSET (FT)	LT/RT	ELEVATIONS LID OR GRATE	ELEVATIONS INVERT	INLETS TY A (EA) W/TY 3V F & G	INLETS TY A (EA) W/TY 20 F & G	INLETS TY A (EA) W / TY 11V F & G	INLETS TY A (EA) W/TY 23 F & G	INLETS TY A (EA) W/TY 8 GRATE	INLETS TY B (EA) W/TY 3V F & G	INLETS TY B (EA) W /TY 11V F & G	INLETS TY B (EA) W / TY 5 OL	INLETS TY B (EA) W/TY 8 GRATE	MANHOLES TY A (EA) W / TY 3V 4' DIA.	MANHOLES TY A (EA) W / TY 3V 5' DIA.	MANHOLES TY A (EA) W / TY 20 5' DIA.	MANHOLES TY A (EA) W/TY5 CL 6' DIA.	MANHOLES TY A (EA) W / TY 3V 6' DIA.	END SECTION (EA) 12"	END SECTION (EA) 15"	END SECTION (EA) 18"	END SECTION (EA) 24"
1L	508+00.00	75.0	LT	N/A	568.27																1		
2L	508+35.4	41.8	LT	572.52	568.64						1												
3L	510+62.11	38.8	LT	571.28	568.90	1																	
4L	510+72.11	38.6	LT	571.28	568.92	1																	
1R	510+62.11	37.8	RT	571.29	568.17	1																	
2R	510+62.11	65.0	RT	N/A	567.89																1		
3R	510+72.11	37.8	RT	571.29	568.25	1																	
4R	510+72.11	65.0	RT	N/A	567.97																1		
5R	511+00.00	61.0	RT	N/A	568.24																1		
6R	511+71	56.0	RT	570.23	568.82					1													
7L	514+28.00	34.8	LT	571.39	568.10	1																	
8L	514+38.00	34.8	LT	571.40	568.06	1																	
7R	513+53.00	53.0	RT	N/A	570.18																1		
8R	514+27.00	53.0	RT	N/A	569.83																1		
9R	514+91.00	53.0	RT	N/A	569.50																1		
10R	515+45.00	53.0	RT	N/A	569.23																1		
11R	516+68.00	53.0	RT	N/A	568.63																	1	
12R	517+22.00	53.0	RT	N/A	568.32																	1	
13R	514+28.00	34.8	RT	571.39	568.07		1																
14R	514+38.00	34.8	RT	571.40	568.03		1																
15R	516+62.00	34.8	RT	571.17	567.04	1																	
9L	518+06.80	34.8	LT	570.35	566.35										1								
10L	548+23.8	53.1	LT	N/A	564.62															1			
16R	518+70.00	35.8	RT	570.02	564.78										1								
11L	533+09.10	34.8	LT	567.68	561.62		1																
12L	533+19.10	34.8	LT	567.68	561.75		1																
13L	536+00.00	34.8	LT	570.35	566.35	1																	
17R	533+09.1	34.8	RT	567.68	561.80	1																	
18R	533+19.1	34.8	RT	567.68	562.08	1																	
19R	534+00.00	34.8	RT	568.03	564.35		1																
20R	536+00.00	34.8	RT	570.35	566.34	1																	
21R	534+00.00	45.0	RT	568.10	564.38								1										
22R	536+00.00	46.8	RT	570.10	566.38								1										
14L	539+80	34.8	LT	571.88	569.31	1																	
23R	539+80.00	34.8	RT	571.88	566.48						1												
24R	539+80.00	50.4	RT	571.36	570.03									1									
15L	542+20.00	34.8	LT	570.02	567.98	1																	
16L	544+20.00	34.8	LT	568.65	566.60	1																	
17L	545+70.00	56.0	LT	565.97	564.64					1													
18L	545+70.00	35.6	LT	567.62	564.43	1																	
19L	547+70.00	34.8	LT	566.27	564.22						1												
25R	542+20.00	34.8	RT	570.02	564.98										1								
26R	542+50.00	51.3	RT	568.51	567.17					1													
27R	544+20.00	34.8	RT	568.65	562.84										1								
28R	545+70.00	34.8	RT	567.64	561.72											1							
29R	547+70.00	34.8	RT	566.27	559.98											1							
30R	547+70.00	37.0	RT	565.27	564.03					1													
20L	549+90.00	37.8	LT	564.72	562.67	1																	
21L	551+40.00	46.0	LT	563.55	560.94	1																	
22L	552+20.00	45.8	LT	563.22	560.54			1															
23L	553+60.00	45.8	LT	562.80	559.84			1															
31R	549+90.00	37.8	RT	564.72	556.59											1							
1M	549+90	7.6	LT	565.22	562.40				1														
2M	549+90	2.9	LT	565.40	562.33				1														
62R	550+00.00	54.0	RT	564.25	563.18					1													
32R	551+40.00	37.8	RT	563.70	555.97											1							
33R	552+50.00	37.8	RT	563.29	555.48											1							
24L	554+47.60	45.8	LT	562.58	559.36			1															
25L	554+57.60	45.8	LT	562.57	555.75							1											

DRAINAGE STRUCTURE SCHEDULE CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE STRUCTURE SCHEDULE

FAP ROUTE 586 (IL 162)
SECTION 60R-2,37R-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: 2/9/2005

2 Rev. Sheet 2-23-05

PLAN | NOTE BOOK NO. | SURVEYED | SCALE | ALIGNMENT CHECKED | ELEVATIONS CHECKED | CADD FILE NAME | BY | DATE

#ROTES#
2/9/2005
c:\pw-projects\vedi0999\plan\hdr-605a.dgn
*DGN:
*REF:
*REF: