

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN TOTAL QUANTITIES	I000-2A	I000-2A	Y031-1F		X020-2A	Y030-1E		
CODE NO	ITEM	UNIT		4 LANE 100% STATE	2 LANE 100% STATE	TRAFFIC SIGNALS IL 162 @ RIGGIN RD. 90% STATE/10% CITY	PARKING LANES 50% STATE 50% CITY Y025		BOX CULVERT SN 060-0403 100% STATE	HIGHWAY LIGHTING 100% STATE	
40600990	TEMPORARY RAMP	SQ YD	550	418	132						
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.2	1.5	4.7						
40800030	AGGREGATE (PRIME COAT)	TON	13.2	3.8	9.4						
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1036	269	767						
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1156	1156							
42001300	PROTECTIVE COAT	SQ YD	6905	4948	1957						
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	188	50	138						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3603	2791	812						
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3952	2377	1575						
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	1877		1877						
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3975		3975						
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1075		1075						
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16,082	9,676	6,406						
44000100	PAVEMENT REMOVAL	SQ YD	1075	1075							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9954	6240	3714						
44000400	GUTTER REMOVAL	FOOT	3985		3985						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	45		45						
44000600	SIDEWALK REMOVAL	SQ FT	2453	895	1558						
44003100	MEDIAN REMOVAL	SQ FT	72		72						
44004250	PAVED SHOULDER REMOVAL	SQ YD	3083	2826	257						
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	676	322	354						
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	143	62	81						
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	175		175						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	24408	22248	2160						
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	7687		7687						
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	10014		10014						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1						
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1						
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1		1						
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1						
50104400	CONCRETE HEADWALL REMOVAL	EACH	5		5						