FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
586	60R-2, 37R-1	MADISON	502	128

STA.   TO STA.

CONTRACT NO.: 76301

NOTES:

1. ALL SIGNS REQUIRED WILL BE SUPPLIED BY THE CONTRACTOR UNLESS OTHERWISE SPECIFIED.

2. THE CONTRACTOR SHALL FURNISH THE POSTS AND ERECT SIGNS AT THE LOCATIONS SHOWN ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.

3. THE HEIGHT TO THE BOTTOM OF THE LOWEST SIGN SHALL NOT BE LESS THAN 6'.

4. THE LOCATION OF THE FLAGGER ON IL 162 SHALL BE NO CLOSER TO THE INTERSECTION THAN STA. 717+20.

5. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED ON THIS PROJECT. THE CONTRACTOR WILL FILL ANY OPEN TRENCH WITH AGGREGATE CAPPED WITH 3" OF BITUMINOUS COLD MIX AT THE END OF THE WORK DAY TO THE SATISFACTION OF THE ENGINEER. COST SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL.
PATCHING OPERATIONS WILL BE COMPLETED WITHIN 48 HOURS OF THE COMPLETION OF THE CULVERT WORK

ROAD CONSTRUCTION AHEAD
W20-1(O)-48
STA. 702+20

ONE LANE ROAD AHEAD
W20-4(O)-48
STA. 707+20

FLAGGER
W20-1101(O)-48
STA. 712+20

PC Sta. 717+50.23

STA. 717+20

718

719

6' X 5' BOX CULVERT

5' X 4' Box Culvert

STA. 100+90

STA. 101+90

FLAGGER
W20-1101(O)-48
STA. 106+72

ONE LANE ROAD AHEAD
W20-4(O)-48
STA. 111+72

ROAD CONSTRUCTION AHEAD
W20-1(O)-48
STA. 116+72

STA. 100+53.5

98+00   HWY 40   99+00   10+100   10+200   HWY 40

IL 162 STA. 719+45.59
IL 40 STA. 100+00

ROAD CONSTRUCTION AHEAD
W20-1(O)-48
STA. 83+40

ONE LANE ROAD AHEAD
W20-4(O)-48
STA. 88+40

FLAGGER
W20-1101(O)-48
STA. 93+40

LEGEND

○   CONE, DRUM OR BARRICADE

⌐   SIGN

◯   FLAGGER

▭   WORK AREA

N

SCALE: 1" = 20'
20'   0   20'   40'

ILLINOIS DEPARTMENT OF TRANSPORTATION
STAGE 2
TRAFFIC CONTROL SPECIAL
LOCATION 2

FAP 586
SECTION 60R-2, 37R-1
MADISON COUNTY

REVISIONS	
NAME	DATE

DRAWN BY:

PLOT DATE: Tuesday August 10, 2004 @ 9:19:22 AM

PLAN

SURVEYED
PLOTTED
ALIGNMENT CHECKED
R/W CHECKED
CADD FILE NAME

NOTE BOOK NO.