

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2585	00-00068-01-WR	COOK	145	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NUMBER 83785				

ITEM#	IDOT PAY ITEM CODE#	PAY ITEM	UNIT	TOTAL QUANTITY	STU ELIGIBLE PARTICIPATING						VILLAGE SPONSORED NON-PARTICIPATING	
					(1) Traffic Signal Meacham @ Tower Road/ McConner Parkway Y031-1F	(2) Traffic Signal Meacham @ Thoreau Y031-1F	(3) Traffic Signal Meacham @ Drummer Y031-1F	(4) Traffic Signal Meacham @ IL Route 62 Y031-1F	(5) Traffic Signal Interconnect Y031-1F	Roadway Lighting Y030-1E		Roadway J000-2A
1	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	451							451	
2	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	37							37	
3	20101000	TEMPORARY FENCE	FOOT	2,200							2,200	
4	20101100	TREE TRUNK PROTECTION	EACH	22							22	
5	20200100	EARTH EXCAVATION	CU YD	18,491							18,491	
6	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8,369							8,369	
7	20400800	FURNISHED EXCAVATION	CU YD	28,756							28,756	
8	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	2,102							2,102	
9	20800150	TRENCH BACKFILL	CU YD	846							846	
10	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2,600							2,600	
11	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,385							1,385	
12	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	23,965							23,965	
13	21300010	EXPLORATION TRENCH SPECIAL	FOOT	200							200	
14	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	478							445	33
15	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	465							445	20
16	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	458							445	13
17	25100630	EROSION CONTROL BLANKET	SQ YD	23,965							23,965	
18	25200110	SODDING SALT TOLERANT	SQ YD	23,965							23,965	
19	25200200	SUPPLEMENTAL WATERING	UNIT	750							750	
20	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	528							528	
21	28000300	TEMPORARY DITCH CHECK	EACH	15							15	
22	28000510	INLET FILTERS	EACH	100							100	
23	28100101	STONE RIPRAP, CLASS A1	SQ YD	6							6	
24	28100107	STONE RIPRAP, CLASS A4	SQ YD	207							207	
25	28200100	FILTER FABRIC FOR USE WITH RIPRAP	SQ YD	213							213	
26	35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	1,605							1,605	
27	35101800	AGGREGATE BASE COURSE, TYPE B, 6"	SQ YD	6,175							5,916	259
28	35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	95							95	
29	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	799							799	
30	40600300	AGGREGATE (PRIME COAT)	TON	16							16	
31	40600990	TEMPORARY RAMP	SQ YD	580							580	
32	40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	1,390								1,390
33	42000501	PORTLAND CEMENT CONCRETE PAVEMENT, 10" (JOINTED)	SQ YD	24,485							24,485	
34	42001100	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	14,327							14,327	
35	42001200	PAVEMENT FABRIC	SQ YD	36,964							36,964	
36	42001300	PROTECTIVE COAT	SQ YD	45,388							45,388	
37	42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,199							1,199	
38	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,169							7,169	
39	44000100	PAVEMENT REMOVAL	SQ YD	40,126							40,126	
40	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	360							360	
41	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15,823							15,823	
42	44000600	SIDEWALK REMOVAL	SQ FT	26,091							26,091	
43	44003100	MEDIAN REMOVAL	SQ FT	30,103							30,103	
44	48200400	BITUMINOUS SHOULDERS 6"	SQ YD	901							901	
45	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	5							5	
46	54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	2							2	
47	54247130	GRATING FOR CONCRETE FLARED END SECTION, 24"	EACH	2							2	
48	550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	1,280							1,280	
49	550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	154							154	
50	550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	64							64	
51	550A0180	STORM SEWERS, CLASS A, TYPE 1, 42"	FOOT	510							510	
52	550A0190	STORM SEWERS, CLASS A, TYPE 1, 48"	FOOT	519							519	
53	550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	1,543							1,543	
54	550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	389							389	
55	550A0400	STORM SEWERS, CLASS A, TYPE 2, 21"	FOOT	140							140	
56	550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	40							40	
57	550A0440	STORM SEWERS, CLASS A, TYPE 2, 33"	FOOT	32							32	
58	55100500	STORM SEWER REMOVAL 12"	FOOT	1,282							1,282	
59	55101400	STORM SEWER REMOVAL 30"	FOOT	40							40	
60	55101500	STORM SEWER REMOVAL 33"	FOOT	32							32	
61	56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	6							6	
62	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2							2	
63	60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH, 4"	FOOT	2,075							2,075	
64	60201340	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5							5	
65	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1							1	
66	60207915	CATCH BASIN, TYPE C, TYPE 11V FRAME AND GRATE	EACH	4							4	
67	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	23							23	
68	60214700	RESTRICTED DEPTH CATCH BASIN, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	4							4	
69	60214714	RESTRICTED DEPTH CATCH BASIN, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3							3	
70	60221100	MANHOLE, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5							5	
71	60223800	MANHOLE, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3							3	
72	60236825	INLET, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3							3	
73	60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	9							9	
74	60250200	CATCH BASINS TO BE ADJUSTED	EACH	3							1	2
75	60251740	CATCH BASIN TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1							1	

Y003

J000-2A
J000-2A

J000-2A

J000-2A

* SPECIALITY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

MEACHAM ROAD
SUMMARY OF QUANTITIES

DESIGNED BY KRY
CHECKED BY RRM

DATE 12/20/04