

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
80	*	LASALLE	460	4

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT  
 \*150-21HBR, 171XIN&TS-1

SUMMARY OF QUANTITIES					URBAN		CONSTRUCTION TYPE CODE			90% FED 10% STATE		
CODE NO.	ITEM	UNIT	TOTAL QTY	80% FED 20% STATE		CONSTRUCTION TYPE CODE			90% FED 10% STATE			
				I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	X771-2A EXIST S.N. 050-0026 PROP. SN 050-0230 I-80	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	1761							1761		
35100100	AGGREGATE BASE COURSE, TYPE A	TON	465	465								
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	3400							3400		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	1430	1,430								
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	470		470							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8415	895						7520		
40600300	AGGREGATE (PRIME COAT)	TON	13	13								
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20								
40600895	CONSTRUCTING TEST STRIP	EACH	3							3		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	181	181								
40600990	TEMPORARY RAMP	SQ YD	136	136								
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	133	133								
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	11176								11176	
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7118		7118							
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	328								328	
42001300	PROTECTIVE COAT	SQ YD	334								334	
42100215	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4"	SQ YD	688								688	
42100815	PAVEMENT REINFORCEMENT 9 3/4"	SQ YD	688								688	
42101300	PROTECTIVE COAT	SQ YD	688								688	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	325	325								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	487	487								
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3839	3839								
44000100	PAVEMENT REMOVAL	SQ YD	25468	5148							20320	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1749	1749								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2372	1086							1286	
44000710	BITUMINOUS BASE COURSE REMOVAL	SQ YD	2938	2938								
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1346	1346								
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4793	4793								
44003100	MEDIAN REMOVAL	SQ FT	2430								2430	
44004250	PAVED SHOULDER REMOVAL	SQ YD	17150								17150	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	196.9	196.9								
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	17.6	17.6								
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	3297	3297								
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2626	146							2480	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	5520	230						5290		
48202850	BITUMINOUS SHOULDERS SUPERPAVE 12 1/2"	SQ YD	5975							5975		
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SQ YD	6460								6460	

\* INDICATES SPECIALTY ITEM

11/1/2004 c:\pro\jects\ed02994\cvs\shf.dgn