

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	LASALLE	460	11
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\*50-2HBR, 171XIN&TS-1

← ACF →

SUMMARY OF QUANTITIES				80% FED 20% STATE			CONSTRUCTION TYPE CODE			ACEM		
CODE NO.	ITEM	UNIT	TOTAL QTY	I 000-2A	J 000-2A	Y 031-IF	I 000-2A	Y 030-1E	I 000-2A	J 000-2A	X 771-2A	
				ROADWAY	ROADWAY	TRAFFIC SIGNALS	STATE ENTRANCE	LIGHTING	ROADWAY		EXIST S.N.	
				IL 351	IL 351	80% FED 10% STATE 10% CITY IL 351	80% FED 20% STATE IL 351	100% CITY IL 351	I-80	I-80	I-80	
* 81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	62			62						
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	77			77						
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	325							325		
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	190							190		
* 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	259			259						
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	910							910		
* 81300510	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 8" X 4"	EACH	2							2		
* 81400400	CONCRETE HANDHOLE	EACH	7			7						
* 81400600	CONCRETE DOUBLE HANDHOLE	EACH	1			1						
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	8182			1427				6755		
* 81600320	UNIT DUCT, WITH 2-1/C NO. 6 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1" DIA., POLYETHYLENE	FOOT	12160							12160		
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1251			1251						
* 81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	30							30		
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2					2				
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	29							29		
* 82109200	SIGN LIGHTING LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM	EACH	5							5		
* 82500520	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 480VOLT	EACH	1							1		
* 83034400	LIGHT POLE, STEEL, 45 FT. M.H., TENON MOUNT	EACH	29							29		
* 83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	25							25		
OO * 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	72							72		
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	13							13		
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	13							13		
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	13							13		
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13							13		
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1							1		
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1							1		
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1							1		
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1						
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	845			845						
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1595			1595						
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2234			2234						
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	41			41						
* 87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	4			4						
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1			1						

\* INDICATES SPECIALTY ITEM  
OO SFTY-3C

11/1/2004 c:\projects\ed02994\cvrsmf.dgn