

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	.	LASALLE	460	12

FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

(50-2)HBR,(71)XN&TS-1

← ACF →

SUMMARY OF QUANTITIES				80% FED 20% STATE		CONSTRUCTION TYPE CODE			ACIM 90% FED 10% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QTY	I 000-2A ROADWAY IL 351	J 000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY IL 351	I 000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y 030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J 000-2A I-80	X 771-2A EXIST S.N. 050-0026 PROP. SN 050-0230 I-80
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1			1					
* 87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT.	EACH	1			1					
* 87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1			1					
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12			12					
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5					
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	52			52					
* 88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	12			12					
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	10			10					
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,790			1,790					
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10000							10000	
X0321472	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	630							630	
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	2	2							
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1-5/8"	FOOT	110								110
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4								4
* X0323885	TRAFFIC SIGNAL BATTERY BACKUP SYSTEM	EACH	1			1					
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	20							20	
X0930400	STORM SEWER WATER MAIN 12"	FOOT	57	57							
X0930600	STORM SEWER WATER MAIN 30"	FOOT	179	179							
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1445	1445							
X3550415	BITUMINOUS BASE COURSE SUPERPAVE 7 3/4"	SQ YD	1493	1493							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	8	8							
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	13	13							
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'D', N70	TON	918	828			90				

* INDICATES SPECIALTY ITEM

11/1/2004 c:\projects\ed02994\cvrshf.dgn