

F.A.I. RTEL.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	LASALLE	460	13

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

*150-21HBR,(7)XIN&TS-1

← ACF →

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QTY	80% FED 20% STATE		CONSTRUCTION TYPE CODE			90% FED 10% STATE		EXIST S.N. PROP. SN
				I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80 % FED 10 % STATE 10% CITY IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	549	549							
X4073061	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9"	50 YD	5300						5300		
X4073201	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 16"	50 YD	7605						7605		
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	10055							10055	
X6050700	REMOVE INLET BOX	EACH	6							6	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	18							18	
* X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4			4					
* X8801345	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2			2					
* X8801350	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2			2					
* X8801395	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2			2					
* X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2			2					
XX005427	STORM SEWER WATER MAIN 36"	FOOT	95	95							
Z0022800	FENCE REMOVAL	FOOT	3395	285						3110	
* Z0002600	BAR SPLICERS	EACH	947								947
□ Z0014700	CULVERT TO BE CLEANED	EACH	8							8	
○ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	4							4	
○ Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4							4	
○ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6							6	
○ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6							6	
Z0047300	PROTECTIVE SHIELD	50 YD	668.4								668.4
Z0050800	REMOVE AND RESET RAISED PAVEMENT MARKERS	EACH	140							140	
X0324878	ADJUSTING SANITARY SEWER SERVICE LINE	EACH	10	10							
X0420500	TEMPORARY PAVEMENT PATCH	50 YD	112.3	112.3							
X0410445	ELECTRICAL CONNECTION TO SIGN STRUCTURE (TRUSS TYPE)	EACH	2							2	
X0324881	INLETS, TYPE A, TYPE IIV FRAME AND GRATE 48" DEPTH	EACH	5							5	
X0404000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE IIV FRAME AND GRATE	EACH	1							1	
* X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	4.5							4.5	
X0324461	ERECTING FLOATING BEARINGS, GUIDED EXPANSION, 125K	EACH	16								16
X0324460	ERECTING FLOATING BEARINGS, FIXED - 250K	EACH	8								8

* INDICATES SPECIALTY ITEM
 □ NON-PARTICIPATING
 ○ SFTY-3N

11/1/2004 c:\p\proj\cts\ed02994\cvr\shr.dgn