

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FA180	(50-2)HBR	LA SALLE	440	19
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CONTRACT NO. 86603

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				I000-2A	J000-2A	X271-2A
X0321472	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	630		630	
X0323558	BRIDGE JOINT SYSTEM (EXPANSION), 1 5/8"	FOOT	108.7			108.7
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4			4
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	20		20	
X4073060	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 9"	SQ YD	5300	5300		
X4073200	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 16"	SQ YD	7605	7605		
X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	10055		10055	
X6050700	REMOVE INLET BOX	EACH	6		6	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	18		18	
Z0002500	BAR SPLICERS	EACH	906			906
Z0011700	CULVERT TO BE CLEANED	EACH	8		8	
Z0021800	FENCE REMOVAL	FOOT	3110		3110	
Z0021999	IMPACT ATTENUATOR REMOVAL	EACH	4		4	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		4	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6		6	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6		6	
Z0047300	PROTECTIVE SHIELD	SQ YD	980.3			980.3
Z0050800	REMOVE AND RESET RAISED PAVEMENT MARKERS	EACH	140		140	
*3001610	ELECTRICAL CONNECTION TO SIGN STRUCTURE (TRUSS TYPE)	EACH	2		2	
*3001611	INLETS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1		1	
*3001620	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	1		1	
*3001621	SEEDING, CLASS 5A (MODIFIED)	ACRE	4.5	4.5		
*3001623	ERECTING FLOATING BEARING, GUIDED EXPANSION - 125K	EACH	16			16
*3001624	ERECTING FLOATING BEARING, FIXED - 250K	EACH	8			8

* INDICATES SPECIALTY ITEM

REVISIONS	NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.I. 80 AT ILLINOIS ROUTE 351

SCALE: NONE DRAWN BY: JDK
DATE: 09/04 CHECKED BY: MTD