

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FA180	(50-2)HBR	LA SALLE	460	24
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

CONTRACT NO. 86603

EROSION CONTROL SCHEDULE

	EROSION CONTROL BLANKET	EARTH EXCAVATION FOR EROSION CONTROL	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	AGGREGATE (EROSION CONTROL)
	SQ YD	CU YD	POUND	EACH	FOOT	EACH	TON
I-80 DITCHES				35		7	
I-80, STA. 636+39.6, 90' LT	7.5						
I-80, STA. 653+97, 81' RT	14.5						
IL 351 DITCHES				10			
IL 351 FORESLOPE NORTH OF BRIDGE					800		
IL 351, STA. 55+18, 74' RT	5						
IL 351, STA. 58+07, 55.8' RT	5						
IL 351, STA. 60+50, 81.5' LT	5						
IL 351, STA. 61+09, 45.3' RT	5						
IL 351, STA. 63+98, 61.7' RT	5						
IL 351, STA. 64+80, 78.1' RT	5						
IL 351, STA. 67+26, 77.4' RT	5						
RAMP E DITCHES				15		2	
RAMP E, STA. 169+30, RT		55					
RAMP E, STA. 171+62, 26.3' RT	10						
RAMP E, STA. 174+70, 59' LT	14						
RAMP E, STA. 174+70, 31' RT	7						
RAMP F DITCHES				25		4	
RAMP F, STA. 128+35, 59' LT	6						
RAMP F, STA. 128+35, 30.2' RT	12						
RAMP F, STA. 135+79, 49.2' RT	14.5	145					
RAMP F, STA. 143+54, 60' RT	11						
RAMP F, STA. 144+52, 60' RT	11	110					
RAMP G DITCHES				19		2	
RAMP G, STA. 243+60, 52.8' LT	12						
RAMP G, STA. 243+60, 32.5' RT	6						
RAMP G, STA. 246+14, 26' RT	6						
RAMP G, STA. 246+88, 32' RT	5						
RAMP G, STA. 252+80, RT		55					
RAMP H DITCHES				21		4	
RAMP H, STA. 266+60, 42' RT	6						
RAMP H, STA. 267+29, 38.4' RT	7.5						
RAMP H, STA. 276+02, 84' LT	6						
RAMP H, STA. 276+02, 36.5' RT	12						
OVER ENTIRE SEEDING AREA			2300				
EARTH STOCKPILES					2000		
AS DIRECTED BY ENGINEER							10
TOTALS	203	365	2300	125	2800	19	10

DRAINAGE REMOVAL SCHEDULE

LOCATION	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL					REMOVING CATCH BASINS	REMOVING INLETS	REMOVE INLET BOX	MANHOLES TO BE FILLED TO MAINTAIN FLOW	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL
			6"	8"	10"	12"	15"					
			FOOT	FOOT	FOOT	FOOT	FOOT					
I-80, STA. 654+00, RT	1	7										
IL-351, STA. 56+25, LT	1		41				1					
IL-351, STA. 56+50, RT	1			41			1					
IL 351, STA. 57+02, RT				50				1				
IL-351, STA. 60+02, LT	1				124							
IL-351, STA. 60+02, RT	1											
IL-351, STA. 64+98, RT	1				66			1				
IL-351, STA. 67+98, RT	1			53				1				
RAMP E, STA. 173+50, LT	1		40					1				
RAMP E, STA. 174+80, LT		100							1			
RAMP E, STA. 179+30, LT	1		36					1				
RAMP F, STA. 128+35, LT	1	63										
RAMP F, STA. 128+35, RT									1			
RAMP F, STA. 135+85, RT	1											
RAMP F, STA. 144+05, RT	1											
RAMP F, STA. 152+90, RT	1											
RAMP G, STA. 242+80, LT		57							2			
RAMP G, STA. 244+50, LT	1											
RAMP G, STA. 246+15, RT									1			
RAMP G, STA. 247+05, RT			28			53	1					
RAMP H, STA. 266+55, RT	1											
RAMP H, STA. 267+30, RT	1											
RAMP H, STA. 274+00, LT								1				
RAMP H, STA. 276+02, LT	1	63									1	
RAMP H, STA. 276+02, RT									1			
ESTIMATED QUANTITY												20
TOTALS	17	290	28	117	144	190	53	3	6	6	1	20

REVISIONS	NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.I. 80 AT ILLINOIS ROUTE 351

SCALE: NONE
DATE: 09/04

DRAWN BY: RJT
CHECKED BY: MTD