F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LASALLE	460	217
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATE	NO. REASON

FILE NAME = $FILE$
PLOT SCALE = $HTSCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE	SUBMITTED	BY	DATE
	PLOTTED		
	GRADES CHECKED		
NOTE BOOK	BASELINE CHECKED		
NO.	STRUCTURE NOTATIONS CHKD		

CHECKS		
INT.	DATE	REASON

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 000-1A ROADWAY	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY	MAIN 2A STATE ENTRANCE 100% STATE	Y030-1E LIGHTING 100% CITY
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	414	414			
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	125	125			
550A2350	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 21"	FOOT	134	134			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	21	21			
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	39	39			
81100700	STORM SEWER REMOVAL 15"	FOOT	363	363			
602219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	12	12			
602212000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
602212000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5			
602212005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
602224700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	20	20			
602224220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	13	13			
602224601	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2			
602285000	MANHOLES TO BE ADJUSTED	EACH	2	2			
602285000	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
602286300	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
602500000	REMOVING MANHOLES	EACH	2	2			
606500C	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,996	2,996			
61101007	STORM SEWERS, PROTECTED, CLASS A, 6"	FOOT	50	50			
61101009	STORM SEWERS, PROTECTED, CLASS A, 8"	FOOT	50	50			
61101011	STORM SEWERS, PROTECTED, CLASS A, 10"	FOOT	50	50			
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2			
61139900	STORM SEWERS, SPECIAL 6"	FOOT	50	50			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE ~~SUMMARY~~ OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT. HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
2601 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM 184-000819
PROFESSIONAL DESIGN FIRM 184-000819 CORPORATION
(217) 793-6364, (217) 793-3177 FAX, (217) 793-3178 TDD

COMPUTER FILE NO. SUMMARY 04
PROJECT 01194.B_N
08/29/04-GSJ