

DESIGN		
INT.	DATE	REASON

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70XN & TS-1)	LASALLE	460	231
STA. _____		TO STA. _____		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 86603				

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D" N70	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8 INCHES	P.C.C. BASE COURSE WIDENING 10"	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	AGGREGATE SHOULDERS TYPE A, 6"	BITUMINOUS SHOULDERS SUPERPAVE 8"	PORTLAND CEMENT CONCRETE SHOULDERS 8"	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A
	GALLON	TON	SQ. YD.	TON	SQ. YD.	TON	TON	SQ. YD.	SQ. YD.	SQ. YD.	TON	SQ. YD.	SQ. YD.	FOOT	FOOT
(IL RTE 351)															
STA. 247+00.00 RT TO STA. 249+16.23 RT	46	1	31	1.3		48	48	31			25	20			216
STA. 247+00.00 LT TO STA. 262+30.70 LT	256	6	1175	9.2	1008	268	236	790		933	34			1340	1320
STA. 249+16.23 RT TO STA. 262+30.70 RT	147	4	591	5.6	1025	155	159	207		927				1403	1104
STA. 262+30.70 LT TO STA. 52+90.57 LT					3181					2655	45		430		157
STA. 262+30.70 RT TO STA. 52+90.57 RT					3137					2603	42		427	96	
(CIVIC ROAD / N 30TH ROAD)															
STA. 43+84.20 LT TO STA. 50+00.00 LT					430				203.0				146		
STA. 43+84.20 RT TO STA. 50+00.00 RT					494				267.0				177		
STA. 50+00.00 LT TO STA. 54+74.86 LT	55	1	240	1.8		57	55	240				102	19		318
STA. 50+00.00 RT TO STA. 54+74.86 RT	49	1	162	2.1		51	51	162				108			339
TOTAL	553	13	2199	20.0	9275	579	549	1430	470	7118	146	230	1199	2996	3297

PLOTS & CHECKS		
INT.	DATE	REASON

FILE NAME	SCALE	DRY	PLOTTED	BY	DATE

CHECKS		
INT.	DATE	REASON

REFLECTOR SCHEDULE	
LOCATION	RAISED REFLECTIVE PAVEMENT MARKERS
	EACH
MAINLINE	
STA. 247+00 TO STA. 252+00	6
STA. 252+00 TO STA. 257+00	9
STA. 257+00 TO STA. 261+00	14
STA. 261+00 TO STA. 266+00	12
STA. 266+00 TO STA. 269+38	15
CIVIC ROAD / N. 30TH ROAD	
STA. 43+84 TO STA. 47+00	7
STA. 47+00 TO STA. 53+00	9
STA. 53+00 TO STA. 54+75	3
TOTAL	75

CULVERT SCHEDULE					
LOCATION	PIPE CULVERTS, CLASS A, TYPE 1				PIPE CULVERTS, CLASS A, TYPE 1 (TEMPORARY) 24"
	15"	18"	24"	EQUIVALENT ROUND SIZE 24"	
	FOOT	FOOT	FOOT	FOOT	
MAINLINE					
STA. 247+80, 32.6' LT.		43			
STA. 249+23, 34.41' LT.		31			
STA. 250+75, 32.42' LT.		23			
STA. 263+47, RT. & LT.			87		
CIVIC ROAD					
STA. 44+95, 28.31' LT.	64				
STA. 46+85, 31.2' LT.				66	
STA. 46+92, 34' RT.	94				
N. 30TH STREET					
STA. 51+05, 23' LT.					20
TOTALS	158	97	87	66	20

SURVEY MARKER SCHEDULE	
LOCATION	PERMANENT SURVEY MARKERS
	TYPE 1
	EACH
MAINLINE	
STA. 253+50.00 (P.O.T.)	1
STA. 258+00.00 (P.O.T.)	1
STA. 262+30.70 (INTERSECTION)	1
CIVIC ROAD	
STA. 40+00.00 (P.O.T.)	1
STA. 45+00.00 (P.O.T.)	1
STA. 55+00.00 (P.O.T.)	1
TOTALS	6

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70XN & TS-1)
LASALLE COUNTY

VERT. SCALE: _____

HORIZ. SCALE: _____

DATE: 08/13/04

DRAWN BY: BISHOP

DESIGNED BY: KUNTZMAN

CHECKED BY: COLBROOK

COMPUTER FILE NO. SCHEDULE.B-04

PROJECT 01194.B.N
08/13/04-RPB

GREENE & BRADFORD, INC.
OF SPRINGFIELD

ENGINEERS AND ARCHITECTS
1000 W. STATE ST. SUITE 100
SPRINGFIELD, ILLINOIS 62760
(618) 266-2000 FAX (618) 266-2001
www.greenebradford.com

FAU 6108 (IL. RTE. 351) LASALLE COUNTY