| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 6108 | (70X)N & TS-1 | LASALLE | 460 | 234 |
| STA. ——— | TO STA. ——— | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

CONTRACT NO. 86603

| DESIGN | | |
|---|---|---|
| INT. | DATE | REASON |

| PLOTS & CHECKS | | | |
|---|---|---|---|
| INT. | DATE | NO. | REASON |

FILE NAME $FILE$
PLOT SCALE $plt-scale$ DRV = $PLOTTER$
PLOT DATE $DATE$
PLOT TIME $TIME$
OPERATOR $USER$

| PROFILE | BY | DATE |
|---|---|---|
| SCRIBED | | |
| PLOTTED | | |
| GRADES CHECKED | | |
| BLUE TOP | | |
| STRUCTURE NOTATNS CHKD | | |

NOTE BOOK NO.

| CHECKS | | |
|---|---|---|
| INT. | DATE | REASON |

## STORM SEWER REMOVAL SCHEDULE

| LOCATION | STORM SEWER REMOVAL 15" |
|---|---|
| | FOOT |
| MAINLINE | |
| STA. 255+56.90, 29.85' LT TO STA. 256+55.37, 30.13' LT | 99 |
| STA. 258+05, 30' LT TO STA. 256+55.37, 30.13' LT | 151 |
| STA. 258+05, 30' LT. TO STA. 258+05, 45' LT. | 15 |
| STA. 258+05, 30' LT TO STA. 258+53, 30' LT | 45 |
| STA. 259+06, 30' LT TO STA. 258+53, 30' LT | 53 |
| | 363 |

## STRUCTURE REMOVAL SCHEDULE

| LOCATION | MANHOLES |
|---|---|
| | EACH |
| STATION 258+05, 30' LT | 1 |
| STATION 258+53, 30' LT | 1 |
| TOTALS | 2 |

## STRUCTURES TO BE ADJUSTED SCHEDULE

| LOCATION | MANHOLES | SANITARY MANHOLES | INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID | INLETS TO BE ADJUSTED W/ NEW TYPE 1 FRAME CLOSED LID |
|---|---|---|---|---|
| | EACH | EACH | EACH | EACH |
| STATION 254+51.04, 40.60' LT | 1 | | | |
| STATION 255+56.90, 29.85' LT | | | | 1 |
| STATION 256+55.37, 30.13' LT | | | 1 | |
| STATION 256+56.26, 17.65' LT | 1 | | | |
| STATION 258+52.91, 45' LT | | 1 | | |
| STATION 261+28.23, 45' LT | | 1 | | |
| TOTALS | 2 | 2 | 1 | 1 |

## PAVEMENT MARKING SCHEDULE

| LOCATION | THERMOPLASTIC PAVEMENT MARKING-LINE 4" | THERMOPLASTIC PAVEMENT MARKING-LINE 6" | THERMOPLASTIC PAVEMENT MARKING-LINE 8" | THERMOPLASTIC PAVEMENT MARKING-LINE 12" | THERMOPLASTIC PAVEMENT MARKING-LINE 24" | THERMOPLASTIC PAVEMENT LETTERS AND SYMBOLS | EPOXY PAVEMENT MARKING-LINE 4" | EPOXY PAVEMENT MARKING-LINE 6" | EPOXY PAVEMENT MARKING-LINE 8" | EPOXY PAVEMENT MARKING-LINE 12" | EPOXY PAVEMENT MARKING-LINE 24" | EPOXY PAVEMENT LETTERS AND SYMBOLS | TEMPORARY PAVEMENT MARKING-LINE 4" | TEMPORARY PAVEMENT MARKING-LINE 6" | TEMPORARY PAVEMENT MARKING-LINE 8" | TEMPORARY PAVEMENT MARKING-LINE 12" | TEMPORARY PAVEMENT MARKING-LINE 24" | TEMPORARY PAVEMENT LETTERS AND SYMBOLS | SIGN PANEL TYPE 1 | TELESCOPING STEEL SIGN SUPPORT |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | FOOT | FOOT | FOOT | FOOT | FOOT | SQ. FT. | FOOT | FOOT | FOOT | FOOT | FOOT | SQ. FT. | FOOT | FOOT | FOOT | FOOT | FOOT | SQ. FT. | SQ. FT. | FOOT |
| MAINLINE | | | | | | | | | | | | | | | | | | | | |
| STA. 247+00 TO STA. 252+00 | 550 | 150 | | | 22 | | | | | | | | 550 | 150 | | | 22 | | | |
| STA. 252+00 TO STA. 257+00 | 604 | 120 | | 202 | | | | | | | | | 604 | 120 | | 202 | | | 16 | 18 |
| STA. 257+00 TO STA. 261+00 | 1,281 | 80 | 40 | 953 | | | 160 | 20 | 80 | | | 15.6 | 1,441 | 100 | 120 | 953 | | 15.6 | 16 | 18 |
| STA. 261+00 TO STA. 266+00 | | | | | | | 2,026 | 100 | 404 | 864 | 84 | 67.6 | 2,026 | 100 | 404 | 864 | 84 | 67.6 | 27 | |
| STA. 266+00 TO STA. 269+38 | | | | | | | 2,046 | 160 | 69 | 668 | | 52.0 | 2,046 | 160 | 69 | 668 | | 52.0 | 31 | 33 |
| CIVIC ROAD / N. 30TH ROAD | | | | | | | | | | | | | | | | | | | | |
| STA. 43+84 TO STA. 47+00 | | | | | | | 1,897 | | 28 | 713 | | | 1,897 | | 28 | 713 | | | | |
| STA. 47+00 TO STA. 53+00 | 942 | | 42 | 380 | | 15.6 | 1,113 | | 353 | | 84 | 46.8 | 2,055 | | 395 | 380 | 84 | 62.4 | | |
| STA. 53+00 TO STA. 54+75 | 1,025 | | | 342 | | | | | | | | | 1,025 | | | 342 | | | | |
| | 4,402 | 350 | 82 | 1,877 | 22 | 15.6 | 7,242 | 280 | 934 | 2,245 | 168 | 182 | 11,644 | 630 | 1,016 | 4,122 | 190 | 197.6 | 90 | 69 |

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 08/13/04

DRAWN BY: BISHOP
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
SIGNAL CONSTRUCTION GRADE
SURVEYING - LANDFILL - LAND
PROFESSIONAL BUILDING PLANS - COST ESTIMATES
ADDITIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 753-8474, (217) 753-8477 (FAX) E-MAIL: GBSPRI@WHEREVER.NET/P-GBSPR

COMPUTER FILE NO. SCHEDULE_B-07
PROJECT 01194_B_N
08/13/04-RPB