

## SUMMARY OF QUANTITIES

SHEET 1 OF 2

LOCATION OF WORK:

FAP 711  
 U. S. RTE. 136  
 STA. 212+81.00A  
 TO  
 STA. 615+79.00

FUNDING BREAKOUT:

TWO LANE RURAL  
 80% FED  
 20% STATE

CONSTRUCTION TYPE CODE:

I000

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY
35101400	AGGREGATE BASE COURSE, TYPE B	TON	307.0	307.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16,433.0	16,433.0
40600300	AGGREGATE (PRIME COAT)	TON	411.0	411.0
40800888	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	2,503.0	2,503.0
40600990	TEMPORARY RAMP	SQ YD	161.0	161.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	944.0	944.0
40800030	AGGREGATE (PRIME COAT)	TON	14.0	14.0
40800040	INCIDENTAL BITUMINOUS SURFACE	TON	642.0	642.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	17,394.0	17,394.0
44000025	BITUMINOUS SURFACE REMOVAL, SPECIAL	SQ YD	3,298.0	3,298.0
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	188,695.0	188,695.0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	61.0	61.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	21.0	21.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	18.0	18.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,666.0	4,666.0
60255500	MANHOLES TO BE ADJUSTED	EACH	17.0	17.0
60266600	VALVE BOX TO BE ADJUSTED	EACH	11.0	11.0
60402510	GRATES, TYPE 11	EACH	8.0	8.0
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	6.0	6.0
67100100	MOBILIZATION	L SUM	1.0	1.0