

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(11,12)RS-2	DEWITT	53	27

CONTRACT NO. 90867

PARTIAL DEPTH PAVEMENT PATCHING (Cont' d)

STATION	DIRECTION	EXISTING OVERLAY THICKNESS	LANE	LENGTH	WIDTH	PARTIAL DEPTH REMOVAL	BITUMINOUS MIXTURE FOR PATCHING
		INCHES		(FT)	(FT)	(SQ YDS)	(TON)
517+52	EB	5.75	DRIVING	6	12	8.0	3.9
517+52	WB	5.75	DRIVING	6	12	8.0	3.9
522+85	EB	5.75	DRIVING	6	12	8.0	3.9
522+85	WB	5.75	DRIVING	6	12	8.0	3.9
529+30	EB	5.75	DRIVING	6	12	8.0	3.9
529+30	WB	5.75	DRIVING	6	12	8.0	3.9
534+79	EB	5.75	DRIVING	4	12	5.3	2.6
534+79	WB	5.75	DRIVING	4	12	5.3	2.6
537+22	EB	5.75	DRIVING	6	12	8.0	3.9
537+22	WB	5.75	DRIVING	6	12	8.0	3.9
541+65	EB	5.75	DRIVING	4	12	5.3	2.6
541+65	WB	5.75	DRIVING	4	12	5.3	2.6
543+60	EB	5.75	DRIVING	6	12	8.0	3.9
543+60	WB	5.75	DRIVING	6	12	8.0	3.9
549+42	EB	5.75	DRIVING	4	12	5.3	2.6
549+42	WB	5.75	DRIVING	4	12	5.3	2.6
549+87	EB	5.75	DRIVING	6	12	8.0	3.9
549+87	WB	5.75	DRIVING	6	12	8.0	3.9
555+77	EB	5.75	DRIVING	6	12	8.0	3.9
555+77	WB	5.75	DRIVING	6	12	8.0	3.9
564+05	EB	5.75	DRIVING	4	12	5.3	2.6
564+05	WB	5.75	DRIVING	4	12	5.3	2.6
564+48	EB	5.75	DRIVING	4	12	5.3	2.6
564+48	WB	5.75	DRIVING	4	12	5.3	2.6
564+90	EB	5.75	DRIVING	4	12	5.3	2.6
564+90	WB	5.75	DRIVING	4	12	5.3	2.6
571+97	EB	5.75	DRIVING	4	12	5.3	2.6
571+97	WB	5.75	DRIVING	4	12	5.3	2.6
572+35	EB	5.75	DRIVING	6	12	8.0	3.9
572+35	WB	5.75	DRIVING	6	12	8.0	3.9
576+78	EB	5.75	DRIVING	6	12	8.0	3.9
576+78	WB	5.75	DRIVING	6	12	8.0	3.9
577+20	EB	5.75	DRIVING	4	12	5.3	2.6
577+20	WB	5.75	DRIVING	4	12	5.3	2.6

SHEET TOTAL = 228.8 111.8