

## SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(11,12)RS-2	DEWITT	53	28

CONTRACT NO. 90867

### PARTIAL DEPTH PAVEMENT PATCHING (Cont' d)

STATION	DIRECTION	EXISTING OVERLAY THICKNESS INCHES	LANE	LENGTH (FT)	WIDTH (FT)	PARTIAL DEPTH REMOVAL (SQ YDS)	BITUMINOUS MIXTURE FOR PATCHING (TON)
580+13	EB	5.75	DRIVING	4	12	5.3	2.6
580+13	WB	5.75	DRIVING	4	12	5.3	2.6
582+57	EB	5.75	DRIVING	6	12	8.0	3.9
582+57	WB	5.75	DRIVING	6	12	8.0	3.9
587+02	EB	5.75	DRIVING	4	12	5.3	2.6
587+02	WB	5.75	DRIVING	4	12	5.3	2.6
587+47	WB	5.75	DRIVING	12	12	16.0	7.8
587+93	EB	5.75	DRIVING	4	12	5.3	2.6
587+93	WB	5.75	DRIVING	4	12	5.3	2.6
588+38	EB	5.75	DRIVING	4	12	5.3	2.6
588+38	WB	5.75	DRIVING	4	12	5.3	2.6
594+06	EB	5.75	DRIVING	4	12	5.3	2.6
594+06	WB	5.75	DRIVING	4	12	5.3	2.6
594+94	EB	5.75	DRIVING	6	12	8.0	3.9
594+94	WB	5.75	DRIVING	6	12	8.0	3.9
601+89	EB	9.25	DRIVING	5	12	6.7	4.6
601+89	WB	9.25	DRIVING	5	12	6.7	4.6
602+31	WB	9.25	DRIVING	4	12	5.3	3.6
608+72	EB	9.25	DRIVING	4	12	5.3	3.6
608+72	WB	9.25	DRIVING	4	12	5.3	3.6
620+23	EB	9.25	DRIVING	4	12	5.3	3.6
620+23	WB	9.25	DRIVING	4	12	5.3	3.6
620+66	EB	9.25	DRIVING	4	12	5.3	3.6
620+66	WB	9.25	DRIVING	4	12	5.3	3.6
621+12	EB	5.75	DRIVING	4	12	5.3	2.6
621+12	WB	5.75	DRIVING	4	12	5.3	2.6
621+55	EB	5.75	DRIVING	4	12	5.3	2.6
621+55	WB	5.75	DRIVING	4	12	5.3	2.6
622+02	EB	5.75	DRIVING	4	12	5.3	2.6
622+02	WB	5.75	DRIVING	4	12	5.3	2.6
622+47	EB	5.75	DRIVING	4	12	5.3	2.6
622+47	WB	5.75	DRIVING	4	12	5.3	2.6
628+89	EB	9.25	DRIVING	4	12	5.3	3.6
628+89	WB	9.25	DRIVING	4	12	5.3	3.6
SHEET TOTAL =						204.5	111.8