

## SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
71	(11,12)RS-2	DEWITT	53	38

CONTRACT NO. 90867

### BITUMINOUS SURFACE REMOVAL (SPECIAL) (Cont' d)

Station	TYPE	Width (FT.)	Radius 1 (FT.)	Radius 2 (FT.)	Area (SQ. YD.)
845+81	LT.	SR 13	10	10	19.21
845+75	RT.	PE, SR 105	10	10	121.44
851+19	RT.	MB 57	-	-	20.00
869+05	LT.	PE 14	20	20	50.19
873+47	LT.	PE 16	15	15	37.40
873+74	RT.	MB 52	-	-	18.33
894+88	RT.	SR 16	20	20	54.63
901+36	RT.	MB 36	-	-	13.00
932+53	RT.	MB	-	-	1.00
932+60	LT.	SR 16	43	43	164.62
932+75	RT.	SR 16	55	55	242.04
933+75	RT.	PE 12	-	-	24.44
972+15	RT.	SR 19	20	20	61.30
972+15	LT.	SR 29	30	30	139.59

SR = Side Road	SUB TOTAL	=	967.19
PE = Private Entrance			
CE = Commercial Entrance	TOTAL	=	3,455.32
FE = Field Entrance			
MB = Mailbox Turnout	USE	=	3,456

### SURVEY MARKERS SCHEDULE

STATION	TYPE	SMCA (EACH)	PSMTBA (EACH)
451+89.50 (BK.)	P. O. T.	1	
603+49.60	P. C.	1	
619+13.40 (BK.)	P. T.	1	
624+81.00	P. C.	1	
648+55.60	P. T.	1	
650+33.95 (BK.)	P. O. T.	1	
773+98.40 (BK.)	P. C.	1	
789+86.80 (BK.)	P. T.	1	
822+71.40	P. C.	1	
827+71.40	P. I.	1	
832+70.60	P. T.	1	
887+16.67 (BK.)	P. C.	1	
893+16.00	P. I.	1	
899+15.80	P. T.	1	
970+49.68 (BK.)	P. C.	1	
TOTAL	=	14	1

SMCA = SURVEY MARKER COVER ASSEMBLY  
 PSMTBA = PERMANENT SURVEY MARKER TO BE ADJUSTED