F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	9

* (58-62,58-62-1,58-63)RS
CONTRACT NO. 90879

SUMMARY OF QUANTITIES (Cont'd)

LOCATION OF WORK: FAI ROUTE 72 (I-72)
SECTION (58-62,58-62-1,58-63)RS
MACON COUNTY

CONSTRUCTION TYPE CODE:				I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	I000
				FAI-72 Macon County Sta 415+07.22 to Sta 468+58.30	FAI-72 Macon County Sta 468+58.30 to Sta 861+36.68	FAI-72 Macon County Impact Attenuators	FAI-72 Macon County SN 058-0068 & SN 058-0069	FAI-72 Macon County SN 058-0070 & SN 058-0071	FAI-72 Macon County SN 058-0074 & SN 058-0075	FAI-72 @ IL 121 Macon County Sta 878+24.32 to Sta 920+60.90
				Rural	Urban	Urban	Urban	Urban	Urban	Urban
				90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
CODE NO	ITEM	UNIT	TOTAL QUANTITY							
X0322729	MATERIAL TRANSFER DEVICE	TON	60887.0	9079.0	51808.0	0.0	0.0	0.0	0.0	0.0
X0324158	COMPUTERIZED GRADE CONTROL SYSTEM	L SUM	1.0	0.5	0.5	0.0	0.0	0.0	0.0	0.0
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	1467.0	0.0	1467.0	0.0	0.0	0.0	0.0	0.0
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	28435.0	3663.0	22823.0	0.0	0.0	0.0	0.0	1949.0
X4066658	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	36454.0	5417.0	31037.0	0.0	0.0	0.0	0.0	0.0
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	1982.0	0.0	718.0	0.0	0.0	0.0	0.0	1264.0
X4430200	REFLECTIVE CRACK CONTROL TREATMENT (SPECIAL)	FOOT	400.0	0.0	400.0	0.0	0.0	0.0	0.0	0.0
X5012650	CONCRETE HEADWALL REMOVAL SPECIAL	EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0
[redacted]										
⚠ X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	40.0	14.0	26.0	0.0	0.0	0.0	0.0	0.0
XX002909	CLASS SI CONCRETE	CU YD	2.3	0.0	2.3	0.0	0.0	0.0	0.0	0.0
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SQ YD	8630.0	0.0	0.0	0.0	2867.0	2096.0	3667.0	0.0
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	27.0	0.0	0.0	0.0	18.0	9.0	0.0	0.0
Z0002600	BAR SPLICERS	EACH	50.0	0.0	0.0	0.0	0.0	0.0	50.0	0.0
Z0002900	BASE COURSE (OPTION)	SQ YD	13253.0	0.0	13253.0	0.0	0.0	0.0	0.0	0.0
Z0004800	BITUMINOUS MIX FOR PATCHING	TON	168.0	168.0	0.0	0.0	0.0	0.0	0.0	0.0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	19.0	0.0	0.0	0.0	4.0	12.0	3.0	0.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	197.0	0.0	0.0	0.0	36.0	17.0	144.0	0.0
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0	0.0	0.0	2.0	0.0	0.0	0.0	0.0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	7.0	0.0	0.0	7.0	0.0	0.0	0.0	0.0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	5.0	0.0	0.0	5.0	0.0	0.0	0.0	0.0
Z0047300	PROTECTIVE SHIELD	SQ YD	2913.0	0.0	0.0	0.0	1147.0	410.0	1356.0	0.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0
Z0066800	STABILIZED SHOULDERS (REPAIR)	SQ YD	26441.1	5366.4	17327.7	0.0	0.0	0.0	0.0	3747.0
Z0075300	TIE BARS	EACH	552.0	55.0	497.0	0.0	0.0	0.0	0.0	0.0
@ Z0076600	TRAINEES	HOURS	1,000		1,000					
*	SPECIALTY ITEMS									

@ 4080

⚠ REVISED 3-1-05