

## GENERAL NOTES (Cont' d)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	MACON	135	4

\* 158-62,58-62-1,58-63)RS  
CONTRACT NO. 90879

## EARTHWORK ANALYSIS

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	FURNISHED EXCAVATION CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
RURAL				
WIDENING FOR TERMINALS				
4 TBT T1 SPECIAL FLARED	0.0	0.0	43.2	- 43.2
0 TBT T1 SPECIAL TANGENT	0.0	0.0	0.0	0.0
TOTALS =	0.0	0.0	43.2	- 43.2
URBAN				
MEDIAN CROSS-OVERS				
STA 555+53.00	113.1	84.8	1.9	+ 82.9
STA 546+00.00	201.9	151.4	331.2	- 179.8
STA 847+50.00	192.7	144.5	202.9	- 58.4
WIDENING FOR TERMINALS				
14 TBT T1 SPECIAL FLARED	0.0	0.0	151.2	- 151.2
4 TBT T1 SPECIAL TANGENT	0.0	0.0	10.4	- 10.4
IMPACT ATTENUATOR				
SN 058-0076	13.0	9.8	599.0	- 589.2
WIDENING FOR TERMINALS @ DUAL STRUCTURES				
6 TBT T1 SPECIAL FLARED	0.0	0.0	844.8	- 844.8
**WIDENING FOR TERMINALS @ OVERHEADS				
12 TBT T1 SPECIAL FLARED	0.0	0.0	260.4	- 260.4
GORE AREAS FOR STAGING				
SN 058-0069	0.4	0.3	0.0	+ 0.3
SN 058-0074	10.5	7.9	0.0	+ 7.9
SN 058-0075	3.0	2.3	0.0	+ 2.3
TOTALS =	534.6	401.0	2401.8	- 2000.8
FINAL TOTALS =	535.0	401.0	2445.0	- 2044.0

EARTHWORK BALANCE = EARTH EXCAVATION X ADJUSTMENT FOR SHRINKAGE (0.75) - EMBANKEMENT

EARTH EXCAVATION = 535.0 CU YD  
FURNISHED EXCAVATION = 2445.0 CU YD

\*\* S.N. 058-0072, 058-0073, AND 058-0076