

### SUMMARY OF QUANTITIES (Cont' d)

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	•	MACON	135	6

• (58-62,58-62-1,58-63)RS  
CONTRACT NO. 90879

LOCATION OF WORK: FAI ROUTE 72 (I-72)  
SECTION ( 58-62, 58-62-1, 58-63)RS  
MACON COUNTY

	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 Macon County	FAI-72 IL 121 Macon County
Sta 415+07.22	Sta 468+58.30	to	Impact	SN 058-0068 & SN 058-0070 & SN 058-0074 &	SN 058-0069	SN 058-0071	SN 058-0075
to	to	Attenuators	SN 058-0069	SN 058-0070	SN 058-0071	SN 058-0075	Sta 878+24.32
Sta 468+58.30	Sta 861+36.68						to
							Sta 920+60.90
Rural	Urban	Urban	Urban	Urban	Urban	Urban	Urban
90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	I000

CODE NO	ITEM	CONSTRUCTION TYPE CODE:	UNIT	TOTAL QUANTITY	I000	I000	SFTY-3N	SFTY-2A	SFTY-2A	SFTY-2A	SFTY-2A	I000
44000500	COMBINATION CURB AND GUTTER REMOVAL		FOOT	336.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	336.0
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)		SQ YD	12884.0	0.0	0.0	0.0	4225.0	3095.0	5564.0	0.0	0.0
44002020	CONCRETE MEDIAN SURFACE REMOVAL		SQ FT	697.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	697.0
44004250	PAVED SHOULDER REMOVAL		SQ YD	13253.0	0.0	13253.0	0.0	0.0	0.0	0.0	0.0	0.0
44004400	PAVEMENT REMOVAL, (SPECIAL)		SQ YD	1000.0	1000.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
44200525	CLASS A PATCHES, TYPE I, 8 INCH		SQ YD	23.0	15.0	8.0	0.0	0.0	0.0	0.0	0.0	0.0
44200529	CLASS A PATCHES, TYPE II, 8 INCH		SQ YD	1681.0	464.0	1217.0	0.0	0.0	0.0	0.0	0.0	0.0
44200533	CLASS A PATCHES, TYPE III, 8 INCH		SQ YD	178.0	16.0	162.0	0.0	0.0	0.0	0.0	0.0	0.0
44200535	CLASS A PATCHES, TYPE IV, 8 INCH		SQ YD	320.0	40.0	280.0	0.0	0.0	0.0	0.0	0.0	0.0
44201741	CLASS D PATCHES, TYPE II, 8 INCH		SQ YD	70.0	0.0	70.0	0.0	0.0	0.0	0.0	0.0	0.0
44201761	CLASS D PATHCES, TYPE I, 10"		SQ YD	32.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	32.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH		SQ YD	625.0	0.0	365.0	0.0	0.0	0.0	0.0	0.0	260.0
44201769	CLASS D PATCHES, TYPE III, 10 INCH		SQ YD	39.0	0.0	39.0	0.0	0.0	0.0	0.0	0.0	0.0
44213000	PATCHING REINFORCEMENT		SQ YD	2201.0	535.0	1666.0	0.0	0.0	0.0	0.0	0.0	0.0
44213200	SAW CUTS		FOOT	16447.0	4314.0	12133.0	0.0	0.0	0.0	0.0	0.0	0.0
44400100	FIBER GLASS FABRIC REPAIR SYSTEM		SQ YD	141.0	0.0	141.0	0.0	0.0	0.0	0.0	0.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B		TON	10921.0	1316.0	9400.0	0.0	0.0	0.0	0.0	0.0	205.0
48202000	BITUMINOUS SHOULDERS SUPERPAVE		TON	35014.0	4230.0	29613.0	0.0	0.0	0.0	0.0	0.0	1171.0
50102400	CONCRETE REMOVAL		CU YD	34.8	0.0	0.0	0.0	0.0	0.0	34.8	0.0	0.0
50104000	BRIDGE RAIL REMOVAL		FOOT	149.0	0.0	149.0	0.0	0.0	0.0	0.0	0.0	0.0
50300100	FLOOR DRAINS		EACH	24.0	0.0	0.0	0.0	0.0	24.0	0.0	0.0	0.0
50300255	CONCRETE SUPERSTRUCTURE		CU YD	40.6	0.0	3.8	0.0	0.9	0.9	35.0	0.0	0.0
50300260	BRIDGE DECK GROOVING		SQ YD	8324.0	0.0	0.0	0.0	2773.0	2002.0	3549.0	0.0	0.0
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I		EACH	19.0	0.0	0.0	0.0	0.0	0.0	19.0	0.0	0.0
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL		POUND	4450.0	0.0	0.0	0.0	0.0	0.0	4450.0	0.0	0.0
50500715	JACK AND REMOVE EXISTING BEARINGS		EACH	19.0	0.0	0.0	0.0	0.0	0.0	19.0	0.0	0.0
50501130	STRUCTURAL STEEL REPAIR		POUND	270.0	0.0	0.0	0.0	0.0	0.0	270.0	0.0	0.0
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	5206.0	0.0	1246.0	0.0	0.0	0.0	3960.0	0.0	0.0
60100060	CONCRETE HEADWALL FOR PIPE DRAINS		EACH	2.0	0.0	2.0	0.0	0.0	0.0	0.0	0.0	0.0