

## SCHEDULE OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	•	MACON	135	22

• (58-62,58-62-1,58-63)RS  
CONTRACT NO. 90879

TABULATION OF CLASS A PAVEMENT PATCHING I-72 WESTBOUND - 8" (CONT'D)

STATION	DIRECTION	LANE	PATCH AREA				SAW CUTS 44213200 (FT)	TIE BARS Z0075300 (EACH)	REINFORCEMENT 44213000 (SQ YD)	REPAIR Z0066800 (SQ YD)	
			LENGTH (FT)	WIDTH (FT)	TYPE I 44200525 (SQ YD)	TYPE II 44200529 (SQ YD)					TYPE III 44200533 (SQ YD)
626+00	WB	DL	6.0	12.0		8.0	60.0	0.0	8.0	68.7	
623+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
621+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
618+50	WB	DL	35.0	6.0			94.0	35.0	23.3	78.3	
592+40	WB	DL	6.0	12.0		8.0	60.0	0.0	8.0	68.7	
577+40	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
572+75	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
572+30	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
569+00	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
569+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
567+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
566+90	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
564+90	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
563+50	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
563+00	WB	DL	25.0	6.0			74.0	25.0	16.7	75.0	
562+25	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
561+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
543+00	WB	DL	12.0	6.0		8.0	48.0	0.0	8.0	70.7	
542+50	WB	DL	8.0	12.0		10.7	64.0	0.0	10.7	69.3	
542+40	WB	DL	25.0	12.0			98.0	25.0	33.3	75.0	
540+25	WB	DL	30.0	6.0			84.0	30.0	20.0	76.7	
532+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
532+00	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
532+00	WB	ML	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
321+00	WB	RL	25.0	6.0			74.0	25.0	16.7	75.0	
316+00	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
316+00	WB	ML	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
314+10	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
312+45	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
311+50	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
311+40	WB	ML	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
310+20	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
309+75	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
309+50	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
301+50	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
300+75	WB	LL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
300+25	WB	LL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
298+50	WB	LL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
296+50	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
281+50	WB	PL	6.0	6.0	4.0		36.0	0.0	4.0	68.7	
281+40	WB	DL	8.0	6.0		5.3	40.0	0.0	5.3	69.3	
269+50	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
265+00	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
262+60	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
262+60	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
260+25	WB	RL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
258+50	WB	RL	12.0	6.0		8.0	48.0	0.0	8.0	70.7	
254+00	WB	LL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
253+30	WB	LL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
230+50	WB	PL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
229+60	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
229+50	WB	DL	4.5	12.0		6.0	57.0	0.0	6.0	68.2	
SHEET TOTALS =			4.0		288.0	76.7	33.3	3060.0	140.0	402.0	3592.7
WESTBOUND FINAL TOTAL =			8.0		817.7	118.0	246.7	8605.0	407.0	1190.3	9892.5