


INTERSECTION OF FAI-72 AND TR 124

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		MACON	135	47
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		• 158-62.58-62-1.58-63IRS		
		CONTRACT NO. 90879		



GUARDRAIL REMOVAL - 63200310

STATION	TO	STATION	LENGTH
RT 15+77.80	TO	18+52.80	275.0
RT 21+19.96	TO	24+32.46	312.5
LT 15+77.80	TO	18+52.80	275.0
LT 21+19.96	TO	24+32.46	321.5
TOTAL = 1184.0 FEET			

STEEL PLATE BEAM GUARDRAIL, TYPE A - 63000000

STATION	TO	STATION	LENGTH
RT 16+96.55	TO	18+21.55	125.0
RT 21+51.21	TO	21+76.21	25.0
LT 17+96.55	TO	18+21.55	25.0
LT 21+51.21	TO	22+76.21	125.0
TOTAL = 300.0 FEET			

TRAFFIC BARRIER TERMINAL, TYPE 6 - 63100085

STATION	TO	STATION	EACH
RT 18+21.55	TO	18+54.70	1
RT 21+18.06	TO	21+51.21	1
LT 18+21.55	TO	18+54.70	1
LT 21+18.06	TO	21+51.21	1
TOTAL = 4 EACH			

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) - 63100167

STATION	TO	STATION	EACH
RT 16+46.55	TO	16+96.55	1
RT 21+76.21	TO	22+26.21	1
LT 17+46.55	TO	17+96.55	1
LT 22+76.21	TO	23+26.21	1
TOTAL = 4 EACH			

